



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202
December 18, 1980

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Ed Cook of Thunderbird Drilling, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Thunderbird Drilling, Inc.

Complete Address: P.O. Box 18407, Wichita, Kansas

Lease Name: Wellman Well No. F-1

Location: SW NE Sec. 31 Twp. 21 Rge. 9 (W)

County: Rice Total Depth: 3570'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated:

Mr. Cook was instructed to plug the well as follows:

8 5/8" - 294' - cem. circ. Fill hole with mud. Pump 50 sacks cement through drill pipe at 450'. Pump 25 sacks cement through drill pipe at 290'. Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement. Cement rat hole with 5 sacks cement.

Very truly yours,

[Signature]
Conservation Division Agent

DEC 24 1980
COMMISSION
CONSERVATION DIVISION
Wichita, Kansas