



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

January 30, 1981

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Don Popp of L.D. Drilling, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Geudessa Oil Corporation

Complete Address: 1125 17th St., Suite 2200, Denver, Colorado

Lease Name: Halton "A" Well No. 1

Location: C NW NW Sec. 31 Twp. 21 Rge. 9 (E) (W)

County: Rice Total Depth: 3540'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Popp was instructed to plug the well as follows:

8 7/8" - 256' - 225 sacks Fill hole with mud. Pump 50 sacks 50-50
Pozmix w/4% gel & 3% cal. chloride through drill pipe at 300'.
Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40'
and cap hole with 10 sacks cement. Cement rat hole with
5 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

FEB - 2 1981

Very truly yours,
CONSERVATION
Wichita, Kansas

Richard J. Torrance
Conservation Division Agent

2-2-81