



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

October 30, 1974

RECEIVED
STATE CORPORATION COMMISSION

NOV 8 1974

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Hildreth of Sterling Drilling Co. has this date requested permission to plug the following described well:

Mr. Hildreth guarantees payment of the plugging fee.

Operator's full Name: Lebsack and Holl

Complete Address: Box 489, Hays, Kansas

Lease Name: Margaret Boy Well No. 1

Location: C W/2 SW Sec. 9 Twp. 21 Rge. 10 (E)(W) X

County: Rice Total Depth 2580' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hildreth was instructed to plug the well as follows:

Fill hole with mud. Push plug to 400' and pump 40 sacks


cement through drill pipe at 400'. Pump 25 sacks cement

through drill pipe at 200'. Push plug and 1/2 sack hulls to

40' and cap hole with 10 sacks cement.

Bridge rathole and cement with 2 sacks cement.

Very truly yours,


Conservation Division Agent