



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

September 29, 1970

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

OCT 7 1970

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. D. B. Pulley of Forbes Casing Pulling, Inc. has this date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Apco Oil Corporation

Complete Address: P.O. Box 1811, Oklahoma City, Oklahoma 73101

Lease Name: Boy Well No. 1

Location: SE SE SW Sec. 9 Twp. 21 Rge. 10 (E) (W) X


County: Rice Total Depth 3508' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Pulley was instructed to plug the well as follows:

Push 5 1/2" plug to 3400'. Fill hole with sand to 3390' and cement with 5 sacks cement. Fill hole with mud to 200'. Set rock bridge from 200' to 190' and cement hole with 25 sacks cement. Fill hole with mud to 10'. Set rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

  
Conservation Division Agent