



15-159-20547-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

March 31, 1974

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAR 28 1975

CONSERVATION DIVISION  
Wichita, Kansas

4-7-75

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Claude Bolt of Mapco, Inc. has this

date requested permission to plug the following described well:

Mr. Bolt guarantees payment of the plugging fee.

Operator's full Name: Mapco, Inc.

Complete Address: 1437 South Boulder, Tulsa, Oklahoma 74119

Lease Name: Sissler Well No. 1

Location: C 5/2 SE Sec. 7 Twp. 21 Rge. 10 (E) (W) X

County: Rice Total Depth 2620' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bolt was instructed to plug the well as follows:

Fill hole with mud. Push plug to 500' and pump 40 sacks  
cement through drill pipe at 500'. Pump 25 sacks cement  
through drill pipe at 240'. Push plug and 1/2 sack hulls to  
40' and cap hole with 10 sacks cement. Bridge rathole and  
cement with 2 sacks cement.

Very truly yours,

Conservation Division Agent