



15.159.21096-0000

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

January 26, 1981

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Roy Goans of Allen Drilling Company has this date requested permission to plug the following described well:

Operator's Full Name: Dakota Resources, Inc.

Complete Address: 2900 Security Life Bldg, Denver, Colorado

Lease Name: O'Neill Well No. 26-2

Location: C SE NW SW Sec. 2 Twp. 21 Rge. 10 (E) (W)

County: Rice Total Depth: 3430'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Goans was instructed to plug the well as follows:

8 5/8" - 294' - Cem. Circ. - Fill hole with mud. Pump 50 sacks
50-50 Pozmix w/4% gel and 3% cat. chloride through drill pipe @ 300'.
Fill hole with mud to 40'. Push plug and 1/2 sack hulls to
40' and cap hole with 10 sacks cement. Cement rat hole
with 5 sacks cement.

Very truly yours,

[Signature]
Conservation Division Agent

JAN 30 1981
CONSERVATION DIVISION
WICHITA, KANSAS

1-30-81