



ROBERT B. DOCKING Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
DALE E. SAFFELS Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-145-20015-0001

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 22 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Zimmerman of Woodman-Iannitti Drlg. has this

date requested permission to plug the following described well:

Mr. Zimmerman guarantees payment of the plugging fee.

Operator's full Name: W. F. Newton

Complete Address: Box 250 Conroe, Texas

Lease Name: Smith Well No. 1

Location: SW SW NW Sec. 16 Twp. 23 Rge. 15 (E)(W) X

County: Pawnee Total Depth 4161 Oil Well     

Gas Well      Washdown And deepen Input Well      SWD Well      D & A X Lost Hole     

Mr. Zimmerman was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540' and displace  
90 sc cement thru drill pipe. Heavy mud to 240' set cementing plug and  
displace 30 sc cement thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole  
with 2 sc cement.

Very truly yours,

Leo A. Mason  
Conservation Division Agent