

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-145-26298-6000

LEASE NAME Campbell

WELL NUMBER 1

SPOT LOCATION c S/2 SE SW

SEC. 19 TWP. 23 RGE. 15W(E) or (W)

COUNTY Pawnee

Date Well Completed 8-1-73

Plugging Commenced 9-4-84

Plugging Completed 9-11-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Range Oil

ADDRESS 240 Page Court, 220 W. Douglas, Wichita, Ks. 67202

PHONE # (316)-265-6231 OPERATORS LICENSE NO. 5120

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Dodge City yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? yes

Producing formation _____ Depth to top _____ bottom _____ T.D. 4074

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	237	8 5/8		
		0	4066	5 1/2		2076

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.
Sand off to 3950. Dump 5 sx cement. Plug 8 5/8 with 3 hulls, 15 gel, 50 sx cement
10 gel, 1 hulls, rubber plug and 100 sx 60/40 pos, 2% gel, 3% cc

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Nicholas Casing Pulling License No. 6698
Address Box 206 Geneseo, Ks. 67444

RECEIVED
STATE CORPORATION COMMISSION

STATE OF _____ COUNTY OF _____, ss.

SEP 17 1984

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Allen D. Nicholas

(Address) _____

SUBSCRIBED AND SWORN TO before me this 14 day of Sept, 1984

STEVEN K. PRICKETT
State of Kansas
My Appt. Exp. Aug. 29, 1985

Steve K. Prickett
Notary Public

My Commission expires: _____

DRILLERS LOG

15-145-20298-0000

No. 1 Campbell

CASING RECORD:	COMPANY: Range Oil Company, Inc.	DESCRIPTION:
6-5/8" @ 237'	CONTRACTOR: Red Tiger Drilling Co.	S1/4 SE 1/4 CS 1/4 SE SW
w/225 sx cement	COMMENCED: July 19, 1973	19-23S-15W
5-1/2" @ 4036'	COMPLETED: August 1, 1973	Pawnee County,
w/150 sx cement		Kansas
TOTAL DEPTH: 4074'		ELEVATION: 2034 Gr.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	170	
Shale	170	240	
Shale & Redbed	240	460	
Sand	460	535	
Shale	535	976	
Anhydrite	976	1008	
Shale	1008	1430	
Shale & Lime	1430	2595	
Shale	2595	2653	
Lime & Shale	2653	3005	
Lime	3005	3115	
Lime & Shale	3115	3250	
Lime	3250	3965	
Lime & Conglomerate	3965	4020	
Lime	4020	4074	

I certify that this is a true and correct of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Linda N. Dickens
Linda N. Dickens

Subscribed and sworn to before me this 3rd day of August, 1973.

Rita H. Frenkle
Notary Public

My Commission Expires:

May 24, 1977

