

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-145-21,034-0000

LEASE NAME Cossman

WELL NUMBER 6

 Ft. from S Section Lir

 Ft. from E Section Lir

SEC. 20 TWP. 23 RGE. 15 XX or (W)

COUNTY Pawnee

Date Well Completed

Plugging Commenced 2-13-92

Plugging Completed 10:30 AM

TYPE-OR PRINT
NOTICE: Fill out complotely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Central Energy Corp.

ADDRESS P.O. Box 47590, Wichita, Ks 67201

PHONE# (316)267-0707 OPERATORS LICENSE NO. 9354

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-13-92 (date)

by Duane Rankin (KCC District Agent's Name)

Is ACO-1 filed? yes If not, is well log attached? NA

Producing Formation Depth to Top 4072 Bottom 4082 T.D. 4114

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	387	0
				5 1/2	4109	1918

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other p were used, state the character of same and depth placed, from feet to feet each

Bottom Plug: Sanded to 4020 & bailed 5 sx Cement.

Top Plug: Pumped 300 lbs Hulls, 10 sx gel, 50 sx C, 10 sx gel, 100 lbs Hulls, wiper plug, & 150 sx 60/40 6% gel. Had max pressure of 550 lbs & shut in of 200 lbs.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 251, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Central Energy Corp RECEIVED

STATE OF Kansas COUNTY OF Barton , ss.


Anna K. Burke

(Employee of Operator) or (Operator

above-described well, being first duly sworn on oath, says: That I have knowledge of the fa statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Anna K. Burke - Sec.

(Address) Box 251, Great Bend, Kansas



SUBSCRIBED AND SWORN TO before me this 13 day of February, 1992

Gary G. Burke
Notary Public

My Commission Expires: 4-30-93