

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-K5-20434-0000

TYPE OR PRINT  
PLEASE FILL OUT COMPLETELY  
AND MAKE REQUIRED AFFIDAVIT.

LEASE NAME Cossman

WELL NUMBER #1

SPOT LOCATION 100' W of SE SE NW

SEC. 20 TWP 23S RGE. 15W(E)OR(W)

COUNTY Pawnee

DATE WELL COMPLETED \_\_\_\_\_

PLUGGING COMMENCED 8-19-83

PLUGGING COMPLETED 8-23-83

LEASE OPERATOR Alpine Drilling Co., Inc.

ADDRESS 200 East First Suite 500 Wichita, Ks. 67202

PHONE #( ) \_\_\_\_\_ OPERATORS LICENSE NO. \_\_\_\_\_

CHARACTER OF WELL \_\_\_\_\_  
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Wichita

Is ACC-1 FILED? \_\_\_\_\_ IF NOT, IS WELL LOG ATTACHED? \_\_\_\_\_

PRODUCING FORMATION \_\_\_\_\_ DEPTH TO TOP \_\_\_\_\_ BOTTOM \_\_\_\_\_ T.D. 4158'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS \_\_\_\_\_ CASING RECORD \_\_\_\_\_

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	355'	none
				4-1/2"	4155'	2009'

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.

Plugged off bottom with sand to 4078' and ran 4 sacks cement. Shot casing @2500', 2400', 2200', 2100', 2012' and layed down a total of 50 joints (2009') of 4-1/2" casing. Plugged well with 3 sacks hulls, 10 sacks gel, 70 sacks 60/40 pos, 2% gel, 3% cc., 10 sacks gel, 1 sack hulls, plug & 125 sacks 60/40 pos, 2% gel, 3% cc. Plugging complete.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE No. 6050

ADDRESS Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, SS.

R. Darrell Kelso (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) R. Darrell Kelso

(ADDRESS) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO BEFORE ME THIS 29 DAY OF August, 19 83



Irene Hoover  
NOTARY PUBLIC  
RECEIVED  
STATE CORPORATION COMMISSION

MY COMMISSION EXPIRES: \_\_\_\_\_

AUG 30 1983  
CONSERVATION DIVISION  
Wichita, Kansas  
FORM CP-4  
REVISED 06-83

8-30-83

STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

15-145-20434-0000

WELL LOG ----- COSSMAN #1  
Located: C SE SE NW, Section 20-23S-15W, Pawnee County, Kansas

OWNER: Alpine Drilling Company, Inc.  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: October 7, 1976  
COMPLETED: 10-15-76

TOTAL DEPTH: 4158'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 95 Sand and Clay	Ran 8 joints 8 5/8", 28# used casing, 343.38' pipe set at 355' K.B. Cemented with 275 sacks Common, 2% gel, 3% cc. Plug down at 7:45 PM, 10-7-76 by Allied.
95 - 356 Shale and Sand	
356 - 986 Shale and Sand - Red Beds	
986 - 1007 Anhydrite	
1007 - 1645 Red Beds and Shale	
1645 - 2049 Shale and Lime Stringers	
2049 - 3808 Lime and Shale	
3808 - 3875 Lime	
3875 - 3960 Lime and Shale	
3960 - 4120 Lime, Shale and Chert	
4120 - 4154 Lime, Shale, Chert, Sand	
4154 - 4158 Arbuckle	Ran 104 joints used 4 1/2", 10.5# casing, 4158.8' set at 4158' K.B. with 150 sacks Common cement. Plug down at 1:00 PM, 10-15-76.

RECEIVED  
STATE CORPORATION COMMISSION

APR 27 1983

CONSERVATION DIVISION  
Wichita, Kansas