

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-113-20-240-A

LEASE NAME Goering

WELL NUMBER 1

660 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 34 TWP. 21S RGE. 3 (X) or (W)

COUNTY McPherson

Date Well Completed 11-23-75

Plugging Commenced 11-1-89

Plugging Completed 11-8-89

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

AMENDED

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE# (918) 494-0000 OPERATORS LICENSE NO. 6568

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on n/a (date)

by Merlan Unruh (KCC District Agent's Name).

Is ACO-1 filled? on old form If not, is well log attached? -

Producing Formation Miss. Depth to Top 3140 Bottom 3413 T.D. 3590

Show depth and thickness of all water, oil and gas formations.

RECEIVED  
 STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

JAN 19 1990

| Formation | Content | From | To   | Size           | Put In      | Pulled out   |
|-----------|---------|------|------|----------------|-------------|--------------|
| Miss.     | Gas     | 3140 | 3413 | 8 5/8<br>4 1/2 | 160<br>3292 | None<br>None |
|           |         |      |      |                |             |              |
|           |         |      |      |                |             |              |

CONSERVATION DIVISION  
 Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from     feet to     feet each set. Dumped sand + 4 sxs cmt from TD to 3100'. Shot pipe @ 2017'. Lost cutting tool in hole. No casing recovered. Pumped down 4 1/2" casing & pressured up to 1000#. Pumped down backside with 2 sxs gel, 120 sxs 60/40 poz + 2% gel. Ran 1" tbg to 510' and pumped 30 sxs cmt. Circ to surf.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P. O. Box 347, Chase, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Company

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Van Valkenburg

(Address) P. O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 17th day of January, 1990

Judith E. Jannell  
 Notary Public

My Commission Expires: March 29, 1992

STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

K.A.R.-82-3-117

API NUMBER 15-113-20,240-A

5.113.20240.0001

LEASE NAME Goering

TYPE OR PRINT

WELL NUMBER 1

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

       Ft. from S Section Line

       Ft. from E Section Line

LEASE OPERATOR Kaiser-Francis Oil Company

SEC. 34 TWP. 21S RGE. 3W (E) (W)

ADDRESS P.O. Box 666 Tulsa, OK 74121-1468

COUNTY McPherson

PHONE#(310) 564-3214 OPERATORS LICENSE NO. 6568

Date Well Completed       

Character of Well Oil

Plugging Commenced 11/1/89

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

Plugging Completed 11/8/89

The plugging proposal was approved on        (date)

by        (KCC District Agent's Name)

is ACO-1 filed?        If not, is well log attached?       

Producing Formation        Depth to Top        Bottom        T.D. 3590'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size  | Put in | Pulled out |
|-----------|---------|------|----|-------|--------|------------|
|           |         |      |    | 8 5/8 | 160    | none       |
|           |         |      |    | 4 1/2 | 3292   | 1600       |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set.

Sanded bottom to 3100' and dumped 4 sacks cement. Shot pipe @20'17'

Pumped down 4 1/2" casing pressured up to 1000#. Pumped down back-

side with 2 sacks gel 120 sacks 60/40 poz 2% gel. Ran 1" tubing 510'

pumped 30 sacks cement 60/40 poz 2% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Company

STATE OF Kansas COUNTY OF Rice

R. Darrell Kelso

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 27 day of Dec., 19 89

My Commission Expires       



IRENE HERZBERG Notary Public  
State of Kansas



# Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone (316) 241-1250

McPHERSON, KANSAS 67460

October 18, 1974

COMPANY: PATRICK PETROLEUM CORPORATION  
 CONTRACTOR: BLACKSTONE DRILLING, INC.  
 FARM: GOERING #1  
 LOCATION: W/2 SE/4 SE/4, Section 34-21S-3W, McPherson County, Kansas  
 COMMENCED: October 10, 1974  
 COMPLETED: October 18, 1974  
 ELEVATION:

|      |    |      |              |
|------|----|------|--------------|
| 0    | to | 125  | Sand         |
| 125  | to | 160  | Shale        |
| 160  | to | 565  | Shale & Lime |
| 565  | to | 810  | Lime         |
| 810  | to | 990  | Lime & Shale |
| 990  | to | 1760 | Shale & Lime |
| 1760 | to | 2025 | Lime & Shale |
| 2025 | to | 2220 | Shale & Lime |
| 2220 | to | 2454 | Sand & Shale |
| 2454 | to | 2845 | Lime         |
| 2845 | to | 2990 | Lime & Shale |
| 2990 | to | 3157 | Shale        |
| 3157 | to | 3160 | Mississippi  |
| 3160 | to | 3180 | Lime         |
| 3180 | to | 3413 | Mississippi  |
| 3413 | to | 3500 | Lime & Shale |
| 3500 | to | 3552 | Shale        |
| 3552 | to | 3556 | Hunton       |
| 3556 | to | 3558 | Lime         |
| 3558 | to | 3590 | Hunton Lime  |
|      |    | 3590 | T. D.        |

RECEIVED  
 STATE OF KANSAS  
 SEP 21 1974

Cut 12 1/4" hole to 160' and run 162.10' of 8 5/8" surface pipe, cemented with 175 sacks of cement at 160'. Plug down at 4:15 P. M., October 10, 1974. Cut 7 7/8" hole to 3590'. Hole dry and abandoned. Filled hole with mud to 175' & set first plug with 25 sacks of cement. Set second plug at 40' with 10 sacks of cement. 2 sacks in rathole. Plugging completed at 12:00 Noon, October 18, 1974. State Plugger, Gilbert Toman, Holyrood, Kansas.

TO: LANSING - 2454'      MISSISSIPPI - 3157'      HUNTON - 3552'

Measurements taken from K. B.

### CERTIFICATE

I, Charles D. Johnson, Secretary-Treasurer of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Goering #1, located on the W/2 SE/4 SE/4, Section 34-21S-3W, McPherson County, Kansas as reflected by the files of Blackstone Drilling, Inc.

  
 Charles D. Johnson, Secretary-Treasurer

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 18th day of October, 1974.

  
 Johnnie L. Schmidt - Notary Public

