


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

McPherson County, Sec. 14 Twp. 21 Rge. 2W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

XX SW SE SE
Lease Owner A. Scott Ritchie
Lease Name Stucky #1 Well No.
Office Address Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plot

Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 12/21/76 19
Plugging completed 12/23/76 19
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Scott
Producing formation Depth to top Bottom Total Depth of Well 3479
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	173	none
				4 1/2"	3038	1804'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded to 2950' and ran 5 sacks cement. Shot pipe at 2461', 2118', 1796', pulled 48 joints. Plugged well with 6 sacks hulls, 30 sacks gel and 150 sacks cement, 50-50 pos 4% gel.

PLUGGING COMPLETE.

DEC 29 1976
12-29-76

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) *R. Darrell Kelso*
CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of December, 19 76

Margaret Melcher
Notary Public.

My commission expires



DRILLERS' WELL LOG

DATE COMMENCED: October 15, 1976
DATE COMPLETED: October 24, 1976

A. Scott Ritchie
"STUCKY # 1"
SW SE SE
Sec 14-T21-R2
McPherson County, Kansas

ELEVATION: 1497 K.B.

0 - 173'	Clay and Sand
173 - 560'	Shale, Lime Streaks, Anhydrite
560 - 2312'	Shale and Lime
2312 - 2951'	Lime
2951' - 3253'	Chert & Lime
3253 - 3324'	Shale
3324 - 3329'	Sand
3329 - 3334'	Lime
3334 - 3421'	Shale
3421 - 3449'	Chert
3449 - 3477'	Sand, Shale, Chert
3477'	RTD

FORMATION TOPS

Lansing	2312
Mississippi	2951
Kinderhook	3253
Misener Sand	3324
Hunton	3329
Maquoketa	3334
Viola	3421
Simpson	3449
RTD	3477

SURFACE PIPE:

Set used 8 5/8", 28# pipe
at 173' w/130 sacks Common,
2% Gel, 3% cc.

PRODUCTION PIPE:

Ran used 4 1/2" casing at 3038'
w/125 sacks 60/40 Pozmix.

RECEIVED
OCTOBER 28 1976
REGISTRATION DIVISION
McPherson, Kansas

A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON) ss.

Wayne Dobbs, of lawful age, does swear and state that the facts and
statements herein contained are true and correct to the best of his knowledge.

Wayne Dobbs

Subscribed and sworn to before me this 26th day of October, 1976.

Dorothy M. Hague
Notary Public

My Commission Expires: April 11, 1978