


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

McPherson County. Sec. 26 Twp. 21 Rge. (E) 2 (W)

Location as "NE/CNW/SW" or footage from lines NE NE NE
Lease Owner Barbara Oil Company
Lease Name Young Well No. 1
Office Address 322 Central Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed November 3, 19 56
Application for plugging filed November 3, 19 56
Application for plugging approved (Orally) November 3, 19 56
Plugging commenced November 3, 19 56
Plugging completed November 3, 19 56
Reason for abandonment of well or producing formation Dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M.A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3510 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	203'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with heavy mud, set bridge at 202' with 20 sacks by Halliburton; set bridge at 35' with 10 sacks by Halliburton, filled to top with soil.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Patton Drilling Company, Inc.
Address Orpheum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
322 Central Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of November, 19 56

[Signature] Notary Public.

My commission expires _____

RECEIVED
STATE CORPORATION COMMISSION
NOV - 6 1956
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 26 T. 21 R. 2W
BOOK PAGE 113 LINE 17

BARBARA OIL COMPANY
 Young #1
 NE NE NE Sec. 26-21-2W
 McPherson County, Kansas

Drilled By: Beardmore Drilling Company
 Drilling Commenced: 10-25-56
 Drilling Completed: 11-3-56

Casing Record:
 205' of 8-5/8" set at 203' with 150 sacks cement on 10-25-56.
 Cement circulated.

Elevation: KB 1490
 DF 1488

<u>FORMATIONS</u>	<u>DEPTH</u>
Cellar	5
Sand	50
Shale and Shells	203
Shale and Shells	500
Shale and Lime	825
Lime and Shale	1140
Lime and Shale	2065
Lime and Shale	2625
Lime and Shale	2815
Lime	2965
Lime	3184
Lime	3250
Lime and Shale	3320
Lime and Shale	3367
Sand	3374
Shale	3413
Shale and Lime	3467
Lime	3510
Rotary Total Depth	3510

TOPS

Lansing	2347
Conglomerate	2959
Mississippi	2993
Kinderhook	3269
Misener	3367
Maquoketa	3373
Viola Lime, Reworked	3467
Solid Viola Lime	3478
Simpson Limestone	3490
Simpson Dolomite	3504


DRILL STEM TEST #1 3360-3374 Open 40 min., very weak blow for 7 min., then quit, flushed tool, had weak blow for 5 min. Recovered 10' drilling mud, no oil. No. IF or FF - IBHP 0 in 20 min., FBHP 660 in 20 min.

STATE OF KANSAS)
 COUNTY OF SEDGWICK) ss

I, the undersigned, being duly sworn on oath state that the above and within statement is a true and correct record and log of the well drilled on the location above described, to the best of my knowledge and belief.

John Beardmore

Subscribed and sworn to before me this 19th day of November, 1956.



Leonard P. Tolle
 Leonard P. Tolle, Notary Public

My Commission Expires:
 January 28, 1960

NOV 21 1956
 CONSERVATION DIVISION
 Wichita, Kansas