


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rice County. Sec. 6 Twp 21S Rge. 8W 0EX (W)
Location as "NE/CNW/SW" or footage from lines C S/2 NE NW
Lease Owner ISERN - WELLS
Lease Name GORE Well No. 1
Office Address BOX 486, Ellinwood, Kansas 67526
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 7 19 67
Application for plugging filed August 7 19 67
Application for plugging approved August 7 19 67
Plugging commenced August 7 19 67
Plugging completed August 7 19 67
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3661 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Red Rock</u>		<u>120</u>	<u>220</u>	<u>8 5/8"</u>	<u>220'</u>	<u>none</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud 200' plug 1/2 sack hulls 25 sacks cement.

Filled hole with mud to 40' plug 1/2 sack hulls 10 sacks cement.

Two sacks in rat hole.

RECEIVED
AUG 9 1967

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor ISERN DRILLING COMPANY
Address Box 486, Ellinwood, Kansas 67526

STATE OF KANSAS, COUNTY OF BARTON, ss.

W. F. Banks (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. F. Banks

Box 486, Ellinwood, Kansas 67526
(Address)

SUBSCRIBED AND SWORN to before me this 8th day of August, 19 67

George A. Meyer
George A. Meyer Notary Public.

My commission expires February 10, 1971.

W E L L L O G

ISERN-WELLS ET AL, GORE #1
 C S/2 NE NW, Sec. 6-21S-8W
 Rice County, Kansas

Figures indicate bottom of formation:

ELEVATION: 1674' KB
 1672' DF
 1670' GL

PIPE RECORD:
 8 5/8" set at 220'
 with 200 sacks cement.

ROTARY COMMENCED: 7-31-67
 ROTARY COMPLETED: 8-7 -67

LOG TOPS:

Heebner	2790
Toronto	2815
Brown Lime	2928
Lansing	2964
Conglomerate Chert	3338
Kinderhook Lime	3391
Miesner Sand	3446
Base Sand	3510
Maquoketa	3519
Viola	3550
Simpson Sand	3598
Arbuckle	3654
Log Total Depth	3661

0 to 10	cellar
120	sand
560	red bed & shale
1250	shale & shells
1505	lime & shale
1676	lime
2055	shale & lime
2580	shale & shales
2831	lime & shale
2900	shale
3250	lime & shale
3340	lime
3484	lime & shale
3548	lime
3661	lime & shale
3661	Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION

AUG 9 1967

CONSERVATION DIVISION
 Wichita, Kansas


STATE OF KANSAS)
 COUNTY OF BARTON) ss

I, Dean Wells, Partner of Isern Drilling Company, contractor for the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matter herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.



 Dean Wells - Partner

Subscribed and sworn to before me on this 8th day of August, 1967.



 George A. Meyer, Notary Public