


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

McPherson County. Sec. 25 Twp. 21S Rge. (E) 3 (W)  
Location as "NE/CNW/SE" or footage from lines SW SW SE  
Lease Owner Greenland Drilling Company  
Lease Name Goering Well No. 1  
Office Address 4722 Broadway, Kansas City 12, Mo.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed 7-7 19 57  
Application for plugging filed 7-7 19 57  
Application for plugging approved 7-7 19 57  
Plugging commenced 7-7 19 57  
Plugging completed 7-7 19 57  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3685 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	209'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Put plug at 195' with 15 sacks cement  
Another plug 15' below cellar and 5 sacks cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Greenland Drilling Company  
Address 4722 Broadway, Kansas City 12, Mo.

STATE OF \_\_\_\_\_ COUNTY OF Sedgwick, ss.  
George H. Bunting, Jr., President (employee of owner) or (owner & operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 12 1957  
CONSERVATION DIVISION  
Wichita, Kansas

(Signature) George H. Bunting, Jr.  
George H. Bunting, Jr., President  
4722 Broadway, Kansas City 12, Mo.  
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of July, 19 57

Verdina B. Rutledge  
Verdina B. Rutledge Notary Public.

My commission expires March 15, 1960

PLUGGING  
FILE SEC 25 T. 21 R. 3 W  
BOOK 26 LINE 45

WELL LOG

Company: GREENLAND DRILLING COMPANY

Sec. 25 Twp 21S Rge. 3W

Farm: GOERING No. 1

Location: SW SW SE  
McPherson County, Kansas

Commenced: 6-25-57

Completed: 7- 7-57

Total Depth: 3685

Contractor: GREENLAND DRILLING COMPANY

Casing: 8-5/8" 209'  
5-1/2" ----

Elevation 1461 RB  
Production: D&A

Figures Indicate Bottom of Formations

50	Clay & sand	TOPS:	
125	Sand	Kansas City	2424
209	Shale & lime	Mississippi	3115
405	Shale & lime	Hunton	3533
615	Lime w/shale streaks	Viola	3650
865	Lime	Simpson	3675
905	Lime & shale	RTD	3685
1940	Shale & lime		
2100	Lime & shale		
2374	Shale & lime		
2378	Brown lime		
2416	Shale & lime		
2498	Lime & shale		
2567	Lime		
2580	Shale & lime		
2644	Lime & shale		
2798	Shale & lime		
2912	Lime & shale		
3111	Shale & lime		
3115	Shale		
3383	Mississippi		
3518	Shale & lime		
3532	Shale		
3538	Lime		
3652	Shale		
3675	Viola		
3685	Simpson shale & sand		
3685	RTD		

STATE OF KANSAS, COUNTY OF SEDGWICK, ss:

I, George H. Bunting, Jr., President of Greenland Drilling Company, upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Goering well.

*George H. Bunting Jr.*  
George H. Bunting, Jr., President

Subscribed and sworn to before me this 11th day of July, 1957.

*Verdina B. Rutledge*  
Verdina B. Rutledge, Notary Public

My commission expires March 15, 1960.

RECEIVED  
STATE CORPORATIONS COMMISSION  
JUL 12 1957  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 25 T. 21 R. 3W  
BOOK PAGE 26 LINE 45