

KANSAS

Form CP-3
Rev. 6-9-67



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 22 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name W. F. Newton 15-145-26015-0001

Complete Address Box 250 Conroe, Texas 77301

Lease Name Smith Well No. 1

Location SW SW NW Sec. 16 Twp. 23 Rge. 15 (E) (W) X

County Pawnee Total Depth 4161

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated Washdown And Deepen Plg om 9-3-67

Plugging Contractor Woodman & Iannitti

Address Wichita, Kansas License No.

Operation Completed: Hour 8:30 A Day 18 Month 1 Year 1968

The above well was plugged as follows:

RTD 4161 8 5/8 csg set at 247 cwc 200 sc.

Gunned pits, circulated heavy mud, set cementing plug at 540' and displaced 90 sc cem. thru drill pipe. Heavy mud to 240' set cementing plug and displaced 30 sc cement thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/22/68
INV. NO. 7122-U

Signed: [Signature]
Well Plugging Supervisor