

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
SEP 8 1967
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name W. F. Newton 15-145-26015-0000

Complete Address: Conroe, Texas

Lease Name Smith Well No. 1

Location SW SW NW Sec. 16 Twp. 23 Rge. 15 (E) (W) X

County Pawnee Total Depth 3705

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Woodman & Iannitti

Address: Wichita, Kansas License No. _____

Operation Completed: Hour 2:45 P Day 3 Month 9 Year 1967

The Above well was plugged as follows:

RTD 3705' 8 5/8 csg set at 250' cwc 200 sc/
Gunned pits, Circulated heavy mud, set cementing plug at 540' and displaced 90 sc cem.
thru drill pipe. Heavy mud to 240' set cementing plug and displaced 30 sc cement thru
drill pipe. Heavy mud to 40' set cementing lpug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Moxey
Well Plugging Supervisor

INVOICED

DATE 9/7/67
INV. NO. 6295-W