

KANSAS

sl
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 18 1972

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Clinton Oil Company 15-145-02461-0000

Complete Address 217 N. Water Wichita, Kansas 67202

Lease Name Albert A. Doerr Well No. 1

Location SE SE SW Sec. 19 Twp. 23 Rge. (E) (W) 15

County Pawnee Total Depth 3902'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 1 P Day 15 Month 7 Year 1972

The above well was plugged as follows:

Total Depth 3902' 13 3/8 csg set at 394' cwc. Cmt. Mat. 50-50 poz cmt W/6% total gel.

5 1/2 csg set at 3900' cw 150 sk cmt.

5 1/2 csg FBTD 3870' with top perf. (3714')

Filled 5 1/2 csg W/sd (3870-3700) dumped 5 sk cmt W/dump bailer. (3665-3700)

Cutoff and recovered 2693' of 5 1/2 csg.

Pumped down 13 3/8 csg with 300 lbs hulls & water -20 sk gel & water -200 lbs hulls

& water -100 sk cmt -15 sk gel & water -20 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Les F. Murray
Well Plugging Supervisor

DATE 7/18/72
INV. NO. 6040-U