

15.009.01/35.00.00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barton County.

Sec. 9 Twp. 18S Rge. 13 (X) W (W)

Location as "NE/CNW/SW" or footage from lines C N/2 NW NE

Lease Owner Sierra Petroleum Co., Inc.

Lease Name EVELEIGH

Well No. 1

Office Address 208 Petroleum Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed 3/3/58 19

Application for plugging filed 3/2/58 19

Application for plugging approved 3/2/58 19

Plugging commenced 3/3/58 19

Plugging completed 3/3/58 19

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Truan - Gorham, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3355 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	745	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING RECORD

Filled hole with heavy mud from 3355' up to 450'. Set bridge with 1/2 sacks hulls, wood plug and 20 sacks cement through drill pipe.
Filled hole with heavy mud up to 250'. Set bridge with 1/2 sack hulls, wood plug and 20 sacks cement through drill pipe. Filled hole with heavy mud up to 40'. Set bridge with 1/2 sacks hulls, wood plug and 10 sacks cement to cellar 0. Job completed 12:00 midnight.

STATE CORPORATION COMMISSION
MAR 15 1958
CONS. DIVISION
Wichita, Kansas
3-13-58

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sierra Petroleum Co., Inc.
Address 208 Petroleum Bldg., Wichita, Kansas

STATE OF KANSAS COUNTY OF RUSSELL, ss.
C. T. Honaker (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. T. Honaker

(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of March, 19 58

My commission expires 1-30-61.

Margie Cooper
Notary Public.

PLUGGING
L SEC 9 T 18 R 13W
BOOK PAGE 86 LINE 45

15.009.01135.00.00

CORRECTED COPY (note location description)

Sierra Petroleum Co., Inc. - Operator

N. C. R. A. - Owner

EVELEIGH #1

C N/2 NW NE Sec 9-18S-13W
Barton County, Kansas

Total Depth: 3355'

Elev: 1815 KB

Comm: 2/21/58

Comp: 3/3/58

Casing:

Cement:

8 5/8 @ 745'

with 350 sacks cement

FORMATION	DEPTH
Shale	235
Shale & sand	240
Shale & red bed	726
Anhydrite	765
Red bed & shale	1165
Shale & salt	1275
Shale & shells	1410
Lime & shale	1975
Shale & shells	2140
Shale & shells	2815
Lime	3010
Lime & shale	3081
Lime	3355
Tops:	
Anhydrite	734
Heebner	2979
Brown Lime	3065
Lansing K. C.	3084
Arbuckle	3314

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

C. T. Houser

Subscribed and sworn to before me this 4th day of March, 1958.

Margie Cooper
Notary Public

My commission expires: 1-30-61.

MAR 13 1958
CONSERVATION DIVISION

PLUGGING
FILE SEC 9 T18 R13W
BOOK PAGE 86 LINE 45