

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas


15.009.01666.00.00
WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 31 Twp. 18 Rge. 11 (X) (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines... CWL N $\frac{1}{2}$ NE $\frac{1}{4}$

Lease Owner... R. H. Shields

Lease Name... Kimpler Lease Well No. 1

Office Address... El Dorado, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)... Dry Hole

Date, well completed... 8/27/41 1941

Application for plugging filed... 8/27 1941

Application for plugging approved... 8/27 1941

Plugging Commenced... 8/27 1941

Plugging Completed... 8/29 1941

Reason for abandonment of well or producing formation... Found Sulphur Water
instead of Oil

If a producing well is abandoned, date of last production... 19

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced?... Yes

Name of Conservation Agent who supervised plugging of this well... C. T. Alexander

Producing formation... Arbuckle Lime Depth to top... 3496 Bottom... 3526 Total Depth of Well... 3526 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Sand	Fresh Water	60	65	20"	65'	
Sand	Water	175	180	15 $\frac{1}{2}$	381'	pulled
Sand	Water	280	295	12 $\frac{1}{2}$	668	"
Sand	Water	335	345	10	1857	"
Lime	Water	1740	1745	8	2260	"
Lime	Water	2075	2085	7	2973	"
Sand	Water	2190	2190	5 $\frac{1}{2}$	3453	"
Lime	Water	2510	2515			
Lime	Water	2620	2625			
Lime	Water	2910	2915			
Lime	Water	3210	3215			
Lime	Water	3245	3250			
Lime	Water	3315	3320			
Lime	Water	3510	3515			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from... feet to ... feet for each plug set.

Filled with cement with cement dump-bailer from 3526 to 3476. Filled with mud from 3476 to 230'. Permanent bridge set at 230'. Filled with cement at 200'. Filled with mud from 200' to 25'. Filled with cement from 25' to 8'. Filled with mud to top of surface.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to... R. H. Shields

Address... Box #85 - El Dorado, Kansas

STATE OF KANSAS, COUNTY OF BUTLER, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)...

R. H. Shields
El Dorado, Kas.

SUBSCRIBED AND SWORN to before me this 30th day of August, 1941

NOTARY PUBLIC

MY COMMISSION EXPIRES FEB. 3, 1944

My commission expires...

F. W. Robinson
Notary Public.

