


Give All Information Completely
Make Required Report to:
Mall or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plugging
off formations.

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 30 Twp. 18 Rge. (E) 11 (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NEc. SE
Lease Owner Lauck & Moncrief
Lease Name Bock Well No. 1
Office Address 520 Fourth Nat'l Bank Bldg. Wichita, Kans.
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed 19
Application for plugging filed June 4 19 45
Application for plugging approved June 4 19 45
Plugging commenced June 4 19 45
Plugging completed June 10 19 45
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Kerr
Producing formation None Depth to top Bottom Total Depth of Well 3485 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	water	3433	3485	10"	165'	cemented none
				5"	3431	2960'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud 3483-3440
Cement 3440-3400
Mud 3400 165
cement 165 135
mud 135 20
cement 20 5' bottom of cellar

PLUGGING
WLF EC 30 18 R-11W
BOOK PAGE 16 LINE 3-6



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Lauck & Moncrief
Address 520 Fourth Nat'l Bank Bldg. Wichita, Kans.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
E. C. Moncrief, (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the leg of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. C. Moncrief
520 Fourth Nat'l Bank Bldg. Wichita Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 19 day of June, 19 45

Elizabeth Gay
Notary Public

My commission expires Sept. 14, 1947

15.009.01311.00.00

LAUCK & MONCRIEF

No.1 Bock

Sec.30 T18S R11W NEc SE $\frac{1}{4}$ Barton County, Kansas.

Commenced April 1, 1945
Completed

Casing: 10" 165' cemented 100 sacks
5" 3431 cemented 50 sacks

Surface	12
Sand & Clay	25
shale	55
shells	70
sand	95
shale & shells	140
shale & redrock	165
shale & shells	450
shale & red rock	675
lime	895
shale & shells	1075
shale	1205
shale & shells	1310
salt	1410
shale & shells	1480
shale	1575
broken lime	1668
lime	1970
lime & shale	2550
shale	2730
lime	3075
shale	3135
lime	3175
lime & shale	3215
Lime	3400
shale & lime	3432
Conglomerate	3434
Lime	3439
Lime (cored)	3445
5' recovery	
Lime	3451
Lime (cored)	3456
4' recovery	
standardized	
3434	3433 derrick floor
3456	3455 " "

Lime	3475
Lime soft	3478
slight increase oil	
Lime	3482
Lime-water	3485

D & A.

Tops Derrick Floor

Ft. Riley	1701
Heebner	2994
Lansing	3126
Conglomerate	3410
Arbuckle	3433
Total Depth	3485

3126

Cleaned out to bottom
no show

Lime 3457
shot 20 qts 3437-86
Rainbow

Lime 3462
Lime soft 3467
show free oil

PLUGGING

FILE # 30-18-R11W

BOOK PAGE-16 LINE 26

