

15.009.20279.00.00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Barton County, Sec. 15 Twp. 18S Rge. 11W ~~12E~~ (W)

Location as "NE/CNW%SW%" or footage from lines SW NW NE

Lease Owner Nadel & Gussman

Lease Name Bieberle Well No. 4

Office Address 1714 First Nat'l Bldg., Tulsa, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 10-5 19 68

Application for plugging filed 10-5 19 68

Application for plugging approved 10-5 19 68


Plugging commenced 10-5 19 68

Plugging completed 10-5 19 68

Reason for abandonment of well or producing formation No commercial quantities of oil or gas encountered.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Donald Truan

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3360 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Water	Surface	271'	8-5/8"		Left in

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fluid to 450, plug, 40 sx cement,
Fluid to 260', plug, 25 sx cement,
Fluid to 40', plug, 1/2 sx hulls, 10 sx cement,
Two sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
OCT 8 - 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Donelson Drilling Company

Address 619 First Nat'l Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF _____, ss.
James L. Donelson (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James L. Donelson
619 First Nat'l Bldg., Wichita, Kans.
(Address)

Subscribed and sworn to before me this 7th day of October, 19 68



Ella Priess
Notary Public.

15.009.20279.00.00

DRILLERS LOG

Nadel & Gussman
#4 Bieberle
SW NW NE, Sec. 15-18-11W
Barton County, Kansas

Elevation: 1769 D.F.
1772 K.B.

Total Depth: 3360'

Commenced: 9-28-68
Completed: 10-5-68

Surface Casing Record:
Ran 271' of 8-5/8" cemented
with 160 sx cement/9-28-68.

Formation

Depth

Surface Hole	271'
Shale	602'
Shale & Salt	1110'
Lime & Shale	3050'
Lime	3360' T.D.

I hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

DONELSON DRILLING COMPANY

James L. Donelson
James L. Donelson

STATE OF KANSAS: ss:

Subscribed and sworn to before me, a Notary Public, in and for said State, this 7th day of October, 1968.

Ella Priess
Ella Priess, Notary Public



My Commission Expires:
August 25, 1972

RECEIVED
STATE CORPORATION COMMISSION
OCT 8 - 1968
CONSERVATION DIVISION
Wichita, Kansas