


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Form CP-4
15-009-19354-0000
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 15 Twp. 16S Rge. 12 (E) (W) X
Location as "NE/CNW/SW" or footage from lines S $\frac{1}{2}$ SW
Lease Owner National Cooperative Refinery Association
Lease Name Ehly Well No. SWD
Office Address P. O. Box 6 Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 7-22-67 _____ 19____
Plugging completed 7-22-67 _____ 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 400 Feet
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10	320	None
				7	None	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Cleaning out cellar. Broke out connections. Squeezed well with 150
sacks of cement.



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 1 day of August, 1967

My commission expires May 27, 1969

Notary Public.

WELL PLUGGING RECORD

NORTH

_____ Barton _____ County, Sec. 15 Twp. 16 Rge. _____ (E) 12 (W)
 Location as "NE/CNWxSWx" or footage from lines S/2, SW/4
 Lease Owner National Cooperative Refinery Association
 Lease Name Whly SWDW Well No. _____
 Office Address P. O. Box 6, Great Bend, Kansas 67530
 Character of Well (completed as Oil, Gas or Dry Hole) SWDW
 Date well completed October 30, 1957
 Application for plugging filed July 5, 1967
 Application for plugging approved July 10, 1967
 Plugging commenced July 22, 1967
 Plugging completed July 22, 1967
 Reason for abandonment of well or producing formation Lease is plugged out.

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation - - - Depth to top - - Bottom - - Total Depth of Well 522 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

RECEIVED
BY THE CONFORMATION COMMISSION

~~AUG 7 1967~~

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.

Address Box 221, Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.
Joseph Hertel (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joseph Hertel
Joseph Hertel
Box #6, Great Bend, Kansas 67530
 (Address)

Box #6, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of August, 1967

My commission expires October 23, 1970

Irene Kelly Marney
Irene Kelly Marney Notary Public.

EMILY S. W. D. WELL
East & North of Beaver
SW 1/4 Sec. 15-16-12N, Barton Co., Kansas

RECEIVED
STATE CORPORATION COMMISSION
JUL 10 1957

CONSERVATION DIVISION
Wichita, Kansas

CASING

FORMATION

7" O.D.

3 ft. cellar

22- 6
19- 2
20- 5
21- 9
22- 2
22- 3
22- 10
22- 11
23- 0
22- 3
22- 6
23- 11
21- 11
20- 7
21- 6
21- 5
23- 3
21- 6
6- 6

3- 12 - Yellow Clay & Rock
12- 135 - Blue Shale & Lime Shells
135- 180 - Gray Shale & Lime Shells
180- 210 - Red bed
210- 225 - Brown Shale
225- 228 - Gray sandy shale) 20 bbl. an hr.
228- 285 - Red bed) Run 8" pipe at 270 ft.
285- 290 - Red Rock
290- 305 - Blue Shale
305- 315 - Red Bed
315- 320 - Gray Shale
320- 325 - Sand H.F.W.
325- 326 - Lime
326- 330 - Sand
330- 370 - Blue Shale) Run 7" pipe at 260 ft.
370- 380 - Shale Lime & Iron
380- 390 - Sandy Shale
390- 442 - Sand H.F.W.) Underreamed to 400 ft & cemented
442- 444 - Lime with 175 sacks of cement, complete
444- 455 - Black Shale around outside of pipe
455- 458 - Lime
458- 460 - Blue Shale
460- 468 - Sandy Shale
468- 490 - Blue Shale
490- 500 - Sandy Shale
500- 505 - Light Blue Shale
505- 515 - Sand & Iron
515- 527 - Lime & Iron
517- 522 - Red Rock

402- 4 over all

5" Liner

26- 0
26- 1
28- 0
24- 10
26- 4

131- 3

Perforated at
all sands

Perforated -

398' to 445
460' to 517

4 1/2
131
5 1/2
131
9 1/2