

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

1
Rice County. Sec. 35 Twp. 231 Rge. 9 (E) (W)
Location as "NE/CNW/SW" or footage from lines MEYME NE/NW/NE
Lease Owner Northeastern Petroleum Company, Inc
Lease Name McVay Well No. 1
Office Address 2400 North Main, Hutchinson, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed November 23, 1964 19
Application for plugging filed December 3, 19 64
Application for plugging approved 19
Plugging commenced 19
Plugging completed 19
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3793 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUR IN	PULLED OUT
216.40'	of 8-5/8" surface casing	left in				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 210 feet 1/4 sack of hulls and plug.
20 sacks of cement
Mud to 40' - 1/2 sack hulls and plug
10 sacks cement - 2 sacks cement in rat hole

RECEIVED
STATE CORPORATION COMMISSION

DEC 4 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Northeastern Petroleum Company, Inc
Address 2400 North Main, Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.

R. R. Dutton (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) NORTHEASTERN PETROLEUM COMPANY, INC,

BY: R. R. Dutton

R. R. Dutton, (Address)

Subscribed and Sworn to before me this 3rd day of December, 19 64

M. L. Bowman

Notary Public.

My commission expires March 4, 1965

MC VAY #1

NE/NW/NE of 35-21-9

Rice County, Kansas

Drilling Contractor - Northeastern Petroleum Company, Inc

Operator - Northeastern Petroleum Company, Inc.,

Date Started - November 13, 1964

Date Finished - November 25, 1964

0	to	165	Surface sand
165	to	180	Sand and red bed
180	to	375	Red bed
375	to	1145	Shale
1145	to	1255	Shale ND SHELLS
1255			
1255	to	1665	Lime and shale
1665	to	1790	Shale w/lime streaks
1790	to	2680	Lime and shale
2680	to	2825	Lime
2825	to	2900	Lime and shale
2900	to	3040	Shale
3040	to	3388	Lime
3388	to	3410	Chert
3410	to	3505	Lime and shales
3505	to	3605	Lime and shale
3605	to	3610	Lime and sand
3610	to	3715	Lime
3715	to	3755	Simpson shale
3755	to	3762	Lime
3762	to	3793	Arbuckle lime.

CASING RECORD

216.40' of 8-5/8" casing - Surface pipe
cemented with 180 sacks of cement

RECEIVED
STATE CORPORATION COMMISSION

DEC 4 1964

CONSERVATION DIVISION
Wichita, Kansas