


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rice County, Sec. 9 Twp. 21S Rge. (E) 9 (W)
Location as "NE/CNW/SW" or footage from lines NW NE SE
Lease Owner C & S Well Servicing Co.
Lease Name Waknitz Well No. 1
Office Address Box 526, Lyons, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 6, 1966
Application for plugging filed January 6, 1966
Application for plugging approved January 6, 1966
Plugging commenced January 6, 1966
Plugging completed January 6, 1966
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well 3550 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	226	8-5/8"	226	-
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Cemented with 140 sacks cement from total depth to 3190 feet; heavy mud from 3190 feet to 240 feet; plug at 240 feet and 40 sacks cement; heavy mud to 40 feet; solid plug and 10 sacks cement to surface; 2 sacks cement in rat hole. Job completed at 8:30 A.M. on 1/1/66.

RECEIVED
STATE CORPORATION COMMISSION

JAN 11 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sage Drilling Co.
Address 500 Bitting Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK
Thomas M. McCaul, Jr. President of Sage Drilling Co.
(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Tom M. McCaul

500 Bitting Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of January, 1966

Louise K. Whitted
Louise K. Whitted - Notary Public.

My commission expires November 26, 1966

DRILLERS LOGWAKNITZ NO. 1

CASING RECORD:	COMPANY:	C & S Well Servicing Co.	DESCRIPTION:
8-5/8" @ 226'	CONTRACTOR:	Sage Drilling Company	NW NE SE
w/185 sacks cement	COMMENCED:	December 30, 1965	Sec. 9-21S-9W
TOTAL DEPTH:	COMPLETED:	January 6, 1966	Rice Co., Kansas
3550'			ELEVATION: 1675 KB
			(Est.)

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Sand	0	254	
Anhydrite	254	270	
Red Bed, Shale & Shells	270	1285	
Shale & Shells	1285	1310	
Shale & Lime	1310	1555	
Lime & Shale	1555	1850	
Shale, Chalk w/Lime	1850	2310	
Shale & Lime	2310	2575	
Lime & Shale	2575	2818	
Shale	2818	2921	
Lime & Shale	2921	2985	
Lime	2985	3015	
Lime & Shale	3015	3550	

RECEIVED
STATE CORPORATION COMMISSION
JAN 11 1966
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge

SAGE DRILLING COMPANY, INC.

By

Thomas M. McCaul, Jr.
Thomas M. McCaul, Jr.

Subscribed and sworn to before me this 6th day of January, 1966.

Louise K. Whitted
Louise K. Whitted - Notary Public

My Commission expires:
November 26, 1966.