

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
APR 8 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Ralph R. Hamilton National Development Corporation

Complete Address: 1300 Union Nat'l Bldg., Wichita, Kansas 67202

Lease Name Mosher Well No. 1

Location NE NE SW Sec. 8 Twp. 21 Rge. 9 (E) (W) X

County Rice Total Depth 3384'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Woodman-Iannitti Drilling Co.

Address: 706 Union Nat'l Bldg., Wichita, Kansas License No.

Operation Completed: Hour 1 PM Day 6 Month April Year 1970

The Above well was plugged as follows:

Hole filled with mud to 195'. Plug and 1/4 sack hulls pushed to 195' and hole cemented
with 25 sacks cement through drill pipe. Hole filled with mud to 40'. Plug and 1/2
sacks hulls pushed to 40' and hole cemented to base of cellar with 10 sacks cement.
Rathole bridged and cemented with 2 sacks cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed:
Well Plugging Supervisor

DATE 4/8/70

INV. NO. 1695-111