

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

*Rec'd
8-21-80*

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -159-20, 929-0000 (of this well)

Operator's Full Name Kennedy & Mitchell, Inc.
Complete Address 7400 W. Jefferson Ave, Denver, Colorado
Lease Name Hxell Well No. 31-519
Location SW NW NE Sec. 14 Twp. 21 Rge. 9 (E) (W) X
County Rice Total Depth 3600'
Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated _____

Plugging Contractor DaMac Drilling, Inc. and Sun Oil Well Cementing Co.
Address Box 1164, Great Bend, Kansas License No. _____

Operation Completed: Hour 2:15 PM Day 13 Month August Year 1980

The above well was plugged as follows: 8 5/8" - 286' - 225 Sacks

Hole Filled with mud. 40 sacks cement pumped through drill pipe at 500'. 25 sacks cement pumped through drill pipe at 280'. Hole Filled with mud to 40'. Plug and 1/2 sack hulls pushed to 40' and hole cemented to base of cellar with 10 Sacks Cement. Rathole cemented with 5 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *[Signature]*
Well Plugging Supervisor

DATE 8-21-80
2918-W