


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rice County. Sec. 14 Twp. 21S Rge. 9 ~~X~~ (W)

Location as "NE/CNW/SW" or footage from lines. C NW SE
Lease Owner H-30, Inc.
Lease Name Brown Well No. 1
Office Address 200 North Main, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 20, 1965
Application for plugging filed July 20, 1965
Application for plugging approved July 20, 1965
Plugging commenced July 20, 1965
Plugging completed July 20, 1965
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3,670 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	210'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from rotary total depth (3,670') to 200'. Set bottom plug at 200' and cemented with 1/4 sack hulls and 20 sacks cement. Filled hole with heavy rotary mud to 40'. Set top plug at 40' and cemented with 1/2 sack hulls and 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 27 1965

CONSERVATION DIVISION
Wichita, Kansas

7-27-65

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor H-30, Inc.
Address 200 North Main, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Garnet B. Douthit (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Garnet B. Douthit
200 North Main, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of July, 19 65

My commission expires December 3, 1968. Geraldine Hays Notary Public.

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY H-31, Inc.

SEC. 14 T. 21S R. 7E
LOC. E NW 33


FARM Brown NO. 1

COUNTY Rice

TOTAL DEPTH 3,670'
COMM. 7-13-55 COMP. 7-20-55

KANSAS

SHOT OR TREATED
CONTRACTOR H-30, Inc.



ISSUED

CASING

20 10
15 5/8' 210' cen w/225 oz
12 6
13 5

ELEVATION 1567 ND

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	90
Red Bed & Shale	212
Red Bed, Shale & Sand	230
Anhydrite	283
Shale & Shells	4105
Lime & Shale	1343
Shale & Lime	1795
Lime & Shale	1525
Shale & Lime	2575
Lime & Shale	2550
Shale & Lime	3351
Lime	3250
Lime & Shale	3451
Sand & Shale	3430
Shale & Lime	3550
Lime & Shale	3575
Rotary Total Depth	3575

RECEIVED
STATE CORPORATION COMMISSION
JUL 27 1955
CONSERVATION DIVISION
Wichita, Kansas

Electric Log Tops

Heebner	2836	-1141
Brown Lime	2741	-1274
Lansing	2772	-1309
Base K. S.	3275	-1559
Conglomerate	3350	-1633
Kinderhook shale	3435	-1712
Kinderhook sand	3451	-1732
Maquoketa	3478	-1811
Viola	3534	-1857
Ginspen	3575	-1900
Arbuckle	3637	-1970
Rotary T. D.	3670	-2003

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-31, INC.

Garnett H. Southit
Garnett H. Southit

STATE OF KANSAS }
 } SS:
SEDGWICK COUNTY }

Subscribed and sworn to before me, a Notary Public in and for said county and state, this 26th day of July, 1955.

Geraldine Hays
Geraldine Hays, Notary Public

My Commission Expires:
December 3, 1958.