

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


OR  
FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plugging  
of formations.

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Rice County. Sec. 6 Twp. 21 Rge. (E) 9 (W)  
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. NW 1/4 NW 1/4 SE 1/4  
Lease Owner. Barnett Oil Company, et al  
Lease Name. Stout Well No. 1  
Office Address. First Nat'l. Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole). Dry Hole  
Date well completed. January 13 19 49  
Application for plugging filed. January 13 19 49  
Application for plugging approved. January 13 19 49  
Plugging commenced. January 13 19 49  
Plugging completed. January 13 19 49  
Reason for abandonment of well or producing formation. Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production. - 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well. Ruel Durkee  
Producing formation. - Depth to top. - Bottom. Total Depth of Well. 3405 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface Pipe				8 5/8"	189 ft.	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Filled hole with heavy mud from 3405 feet to 175 feet. Set plug at 175 feet and filled surface casing with cement to 125 feet. Filled surface casing with heavy mud from 125 feet to 15 feet. Set plug at 15 feet and filled casing with cement to bottom of cellar.

RECEIVED  
Conservation Div.  
JAN 22 1949  
STATE CORPORATION  
COMMISSION  
KANSAS

1-22-49

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. Barnett Oil Company  
Address. 117 First National Bank Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
W. R. Hunter (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *W. R. Hunter*

First Nat'l. Bank Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of January, 19 49

*Adelaide Olivier*  
Notary Public.

My commission expires 5/12/51

PLUGGING  
FILE REC. 6 T 81 R 9 W  
BACK PAGE 80

BARNETT OIL COMPANY, ET ALLOG OF STOUT WELL NO. 1NW $\frac{1}{4}$ .NW $\frac{1}{4}$ .SE $\frac{1}{4}$  SECTION 6-21S-9W, RICE COUNTY, KANSAS

Formation	From	To	Remarks
Surface Sand	0	35	
Water Sand	35	50	
Red Rock	50	70	
Red Bed	70	155	
Shale	155	189	Set 8 5/8" Surface Pipe at 189 feet, cemented with 200 sacks of cement.
Red Bed	189	275	
Anhydrite	275	295	
Shale and Shells	295	710	
Shale, Shells and Salt	710	1130	
Shale and Shells	1130	1215	
Lime and Shale	1215	1375	
Sand	1375	1420	
Shale and Lime	1420	1640	
Broken Lime and Shale	1640	1765	
Lime	1765	1845	
Shale	1845	1850	
Lime and Shale	1850	1900	
Sandy Shale	1900	2080	
Broken Lime	2080	2100	
Shale	2100	2240	
Lime	2240	2300	
Lime and Shale	2300	2430	
Broken Lime	2430	2520	
Lime	2520	2600	
Lime and Shale	2600	2740	
Lime	2740	2830	
Shale and Shells	2830	2915	
Shale and Lime	2915	2985	
Lime	2985	3062	
Lime and Shale	3062	3105	
Lime	3105	3290	
Lime and Shale	3290	3380	
Lime	3380	3405	
Total Depth		3405	Dry and abandoned.

**RECEIVED**

Conservation Div.

JAN 22 1949

STATE CORPORATION  
COMMISSION  
KANSAS

**PLUGGING**  
 FILE SEC 6-T-21R-9S  
 ROCK PAGE 80 LINE 4