


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rice County. Sec. 13 Twp. 21S Rge. 8 (E) 8 (W)
Location as "NE/CNW/SW" or footage from lines NW NW
Lease Owner Aspen Resources, Ltd.
Lease Name Coyne Well No. 1
Office Address Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 25 19 70
Application for plugging filed December 22 19 70
Application for plugging approved December 23 19 70
Plugging commenced January 18 19 71
Plugging completed January 22 19 71
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3390 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back to 3350', dumped 5 sacks cement; Set bridge at 215' to 200',
dumped 35 sacks cement back into the surface casing; Mudded to 40',
10 sacks of cement to surface.

RECEIVED
STATE CORPORATION COMMISSION
FEB 24 1971
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pawnee Drilling Co., Inc.
Address P. O. Box 783, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Robert L. Pelster (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) [Signature]
Robert L. Pelster, Great Bend, Kansas
(Address)



Subscribed and sworn to before me this 19th day of February, 19 71

Theora Holleman
Theora Holleman Notary Public.

DRILLERS LOG

COMPANY: Aspen Resources, Ltd.
 CONTRACTOR: Aspen Drilling Co.
 LEASE NAME: Coyne #1
 LOCATION: NW-NW Sec. 13-T21S-R8W
 Rice County, Kansas
 ELEVATION: 1634 K.B.
 SURFACE CASING: 4 jts. (137') 8 5/8"
 OIL STRING: 105 jts. (3378') 5 1/2"
 COMMENCED: September 20, 1970
 COMPLETED: September 25, 1970
 ROTARY TOTAL DEPTH: 3364'

<u>FORMATION</u>	<u>DEPTH</u>	
Shale & Shells	250	Ran 4 jts. (137') 8 5/8" casing set
Shale	1400	at 142' with 150 sacks cement.
Shale & Shells	1540	Cement circulated.
Anhydrite	1588	
Red Bed	1700	Ran 105 jts. (3378') 5 1/2" casing
Shale & Shells	2150	set at 3363 1/2' with 75 sacks.
Shale & Lime	3165	

AFFIDAVIT

State of Kansas)
) ss:
 County of Barton)

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 23 1970
 CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, being duly sworn on oath, states that the above statement and log are a true and correct record and log of the well drilled at the location above described.

William S. Schachle
 William S. Schachle, AFFIANT

Subscribed and sworn to before me this 26th day of September, 1970.

Theora Holleman
 Theora Holleman, Notary Public

My commission expires: April 18, 1972.

