

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 N. 4th Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

-6-			
	26		

Locate well correctly on above
Section Plat

Rice County. Sec. 26 Twp. 21S Rge. (E) 8 (W) 8
Location as "NE/CNW/SW" or footage from lines C NW NE
Lease Owner E. H. Adair Oil Co.
Lease Name McFarland "B" Well No. 1
Office Address 1005 E. Second, Wichita, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4-16-63 19
Application for plugging filed 4-16-63 19
Application for plugging approved 4-16-63 19
Plugging commenced 4-16-63 19
Plugging completed 4-16-63 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well 3367 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	845/8 275	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 270', plug, hulls and 20 sax cement thru drill pipe.

Mud to 35', plug, hulls and 10 sax cement.

2 sax cement in rathole.

RECEIVED
STATE CORPORATION COMMISSION

APR 26 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor E. H. Adair Oil Co.
Address 1005 E. Second, Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
K. W. Johnson (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) K. W. Johnson
Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of April, 19 63

My commission expires 9-15-65

Notary Public.

E. H. Adair Oil Company
1005 East Second Street
Wichita 14, Kansas.

E. H. Adair Oil Company
McFarland "B" - No. 1
C - NW $\frac{1}{4}$ of NE $\frac{1}{4}$ of
Sec. 26-21S-8W.
Rice County, Kansas.

Elevation: 1,635 K.B.

Comm.: 4- 8-63
Comp.: 4-15-63
Contractor:
E. H. Adair.
8-5/8 in. s/csg. @
275 ft. w/275 sax.
Pro. D. & A.

Figures indicate bottoms of formations:

Shale and lime to	2700	Shale	to	3224
Lime	2763	Lime		3261
Black shale	2768	Shale		3267
Lime	2771	Lime		3279
Shale	2781	Shale		3289
Lime	2792	Lime		3300
Shale	2912	Shale		3304
Lime	2928	Lime		3312
Shale	2944	Shale		3323
Lime	2951	Lime		3328
Shale	2954	Shale		3340
Porous lime	2965	Lime		3345
Lime	3111	Shaley lime		3354
Shaley lime	3124	Shale, green		3357
Lime	3132	Cherty conglomerate		3359
Shale	3135	Chert, show oil		3367
Lime	3221	R.T.D.		3367

Formation Tops:

HEEBNER SHALE	2763 (-1128)
DOUGLAS SHALE	2792 (-1157)
BROWN LIME	2912 (-1277)
LANSING-K.C. LIMESTONE	2944 (-1309)
PENNSYLVANIAN CONGLOMERATE	3357 (-1722)
MISSISSIPPI CHERT	3359 (-1724)

DST #1, 3343-67: Weak blow for 90 minutes. Recovered 60 feet rotary mud.
IBHP - 81 lbs. in 20 minutes;
FBHP - 81 lbs. in 30 minutes;
IFP - 45 lbs.
FFP - 62 lbs.
Results of this drill-stem test were conclusive, and it was not considered necessary to run an electric-log.
The hole was abandoned and plugged at a depth of 3,367 ft.

Certified correct:

K. W. Johnson
K. W. Johnson Geologist.

RECEIVED
STATE CORPORATION COMMISSION

APR 26 1963

CONSERVATION DIVISION
Wichita, Kansas