


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Form CP-4

15-009-03309-00-00

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines Barton County. Sec. 14 Twp. 16 Rge. 12 (E) W (W)
Lease Owner Thor Corporation
Lease Name Hoffman Well No. 1
Office Address Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 12-27-63 _____ 19____
Plugging completed 1-3-64 _____ 19____
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3381 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	262'	None
				5-1/2"	3379'	2740'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, sanded hole and dumped 5 sacks of cement with dump bailer. Pulled 5 1/2" casing, bailed hole to 282', set rock bridge to 272' and dumped 30 sacks of cement @ 272'. Mudded hole to 30', set rock bridge and ran 10 sacks of cement to cap well.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING COMPLETE.

JAN 13 1964

CONSERVATION DIVISION
Wichita, Kansas

1-13-64

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of January, 1964

My commission expires May 20, 1964

Milton J. Volin

Notary Public.

15-009-03309-00-00

Q

B & R DRILLING, INC.
HOFFMAN #1

SE NW SW Sec. 14-16S-12W
BARTON COUNTY, KANSAS

TOTAL DEPTH: 3381 on Original Completion
Drilled deeper to 3383

Started: September 2, 1950
Completed: September 19, 1950

8 5/8" Surface Casing set @ 262' w/ 150 sacks cement.
5 1/2" Casing set @ 3379' w/ 100 sacks cement.

ADDITIONAL INFORMATION:

Open Hole:	3379-83
Plugged back to	3380
Bridge Plug	3330
Perforated	3290-96
"	3274-78
"	3252-60
Bridge Plug	3200
Perforated	3162-66
"	3138-44

FORMATION	THICKNESS	DEPTH
Shale-Shells-Sand		180
Shale-Shells		220
Shale-Red Bed		262
Shale-Shells		430
Sand-Iron-Shale		535
Shale-Shells		550
Red Bed		780
Shale-Blue		802
Anhydrite		820
Shale-Red Bed-Shells		985
Shale-Shells		1235
Salt		1450
Lime-Shells-Shale		1550
Lime-Shale		1925
Shale-Sandy Lime		1968
Lime-Shale		2715
Lime		3080
Shale		3110
Lime		3265
Lime		3305
Lime-Shale		3377
Conglomerate		3380
Arbuckle		3381

RECEIVED
STATE CORPORATION COMMISSION

DEC 24 1950

CONSERVATION DIVISION
Wichita, Kansas