

15-009-05938-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittig Building
Wichita, Kansas

Barton

County. Sec. 14 Twp. 16S Rge. 12W (E) (W)

T 16s NORTH R 12w

Location as "NE/CNW/SW" or footage from lines SE NW NE

Lease Owner J. E. Day, Agent

Lease Name Feltes Well No. 8

Office Address Box 7 - Eldorado, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil well

Date well completed October 24 1951

Application for plugging filed September 19 1955

Application for plugging approved September 20 1955

Plugging commenced September 23 1955

Plugging completed September 27 1955

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren Horner

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3350 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	501'	None
				5-1/2"	3338'	2671'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled the hole with sand from 3350' to 3330' and ran 5 sacks of cement. Mudded the hole to 250', set a 10' rock bridge and ran 20 sacks of cement. Mudded the hole to 35', set a 10' rock bridge and ran 5 sacks of cement on top. Plugging completed.

RECEIVED
STATE CORPORATION COMMISSION

OCT 17 1955

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.

Address Chase, Kansas

STATE OF Kansas COUNTY OF Barton ss.

J. E. Day, Agent (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. E. Day
Box - 7 - Eldorado, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 8 day of October, 19 55

Laura Hall
Notary Public.

My commission expires Sept 24, 1959

PLUGGING
FILE SEC-14 T-16 R-12W
BOOK PAGE 2 LINE 25

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15-009-05938-00-00


Company- J. E. DAY
Form- Feltes

No. 8

SEC. 14 T. 16 R. 12W
SE NW NE

Total Depth. 3350
Comm. 10-12-51 Comp. 10-24-51
Shot or Treated.
Contractor. Pam-Kar Drlg. Co., Inc.
Issued. 2-16-52

County Barton
KANSAS



Elevation. 1906 D.F.

Production. dry

CASING:

8 5/8" 501'
5 1/2" 3338'

Figures Indicate Bottom of Formations.

surface soil, rock,	
clay	40
shale	110
sand	120
shale, shells	232
sand	250
shale sandy	382
sand	442
pyrite	445
pyrite & shale	504
shale, shells	520
sand	545
shale, redbeds	788
anhydrite	815
shale, shells	900
redbed	1020
shale, shells	1170
salt	1460
shale, shells	1515
shale, lime	1810
lime broken	1920
lime	2005
lime, shale	2960
lime, shale, sand	3035
lime, shale	3227
lime	3269
lime, shale, chert	3301
lime	3333
lime, shale	3339
lime, shale	3350
Total Depth	

Tops: Scout.	
Heebner	2976
Brown Lime	3066
Lansing	3080
Conglomerate	3332
Arbuckle	3337
Reagan Sand	3340

PLUGGING
WELL SEC 14 T 16 R 12W
BOOK PAGE 2 LINE 25

RECEIVED
KANSAS GEOLOGICAL SOCIETY
DIVISION