


15-009-05964-0000

STATE OF KANSAS CORPORATION COMMISSION

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 800 Bittling Building Wichita, Kansas

WELL PLUGGING RECORD

Barton County. Sec. 14 Twp. 16 Rge. 12 (E) W (W) Location as "NE/CNW 1/4 SW 1/4" or footage from lines SE NE NW Lease Owner B & R Drilling, Inc. Lease Name Theisen Well No. 1 Office Address Russell, Kansas Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole Date well completed 12-3-50 Application for plugging filed 1-12-51 Verbally 19 Application for plugging approved 1-12-51 " 19 Plugging commenced 1-13-51 19 Plugging completed 1-17-51 19 Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Flat

If a producing well is abandoned, date of last production 19. Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough Producing formation Depth to top Bottom Total Depth of Well 3361 Feet Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: 8 5/8", 255', None. Row 2: 5 1/2", 3359', 1819'.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugging Record

Plugged back with crushed rock from 3220' to 3075'. Dumped 5 sac cement at 3075' with dump bailer. Top of cement 3040'. Filled hole with mud to 255', set rock bridge, dumped 15 sac cement. Top of cement 210'. Filled with mud to 30', set rock bridge, dumped 10 sa-x cement fro cap.

RECEIVED STATE CORPORATION COMMISSION IAN 25 1951 CONSERVATION DIVISION WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to B. & R. Drilling, Inc. Address Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss. W. A. Michaelis, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. A. Michaelis, Jr. Russell, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 24th day of January, 1951 Notary Public.

My commission expires 6-17-54

PLUGGING FILE SEC 14 T 16 R 12 BOOK PAGE 56 LINE 39

A. & H. Drilling, Inc.
Barton County, Kansas
Theisen # 1

SE NE NW Sec. 14 - 16- 12

15-009-05964-00-00

Total Depth: 3361'
Comm: 11-19-50
Comp: 12- 3-50

Casing

Cement

8 5/8" set @ 255'
5 1/2" set @ 3359'

150 Sacks of Cement
100 Sacks of Monarch

Formation	Depth:
Surface & Post Rock	40
Soft rock-Sand-Shale	243
Shale	255
Shale-Shells	310
Sand	350
Shale-Shells-Sand	480
Shale-Shells	540
Red Bed	720
RedBed-Shale	805
Anhydrite	855
Shale-Shells	1236
Salt	1450
Shale-Shells-Lime	1575
Lime-Shale	1805
Lime	1910
Lime-Shale	2260
Shale-Shells	2370
Lime-Shale	2605
Shale-Lime	2735
Lime	2805
Lime-Shale	2870
Lime	3060
Lime-Shale	3086
K. C. Lime	3110
Lime	3155
Lime	3332
Shale	3338
Conglomerate Sand	3344
Conglomerate	3359
Arbuckle	3361

RECEIVED
STATE CORPORATION COMMISSION
JAN 25 1951
CONSERVATION DIVISION
Topeka, Kansas

STATE OF KANSAS)
)SS
RUSSELL COUNTY)

I hereby certify that the above information is true and correct to the best of my knowledge.

Violet Keller

Subscribed and sworn to before me this 12th day of December, 1950

PLUMBING
FILE SEC. 14 T. 46 R. 12W
BOOK PAGE 56 LINE 39

Clayton L. ...

Notary Public

My commission expires: 6-17-51