


15.009.01555.00.00

All information completely
be required and
of Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 1 Twp. 17S Rge. 13W (E) (W)
Location as "NE/CNW/SW" or footage from lines SW SE NW
Lease Owner R. W. Womer
Lease Name Reif Well No. 1
Office Address Box 394, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1-1-64 19
Application for plugging filed 1-1-64 19
Application for plugging approved 1-1-64 19
Plugging commenced 1-1-64 19
Plugging completed 1-1-64 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3455 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	300'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 300' with 25 sacks cement in barrel through drill pipe
Top plug @ 40' with 40' with 1/2 sack hulls & 10 sks. cement
2 sacks in rathole.

RECEIVED
STATE CORPORATION COMMISSION

JAN 7 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite
Box 486, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 6th day of January, 1964.

My commission expires April 1, 1967 Ulanda Nichols Notary Public.

15.009.01555.00.00

DRILLER'S LOG

COMPANY: R. W. Womer
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: REIF #1
 LOCATION: SW SE NW Sec. 1-17S-13W
 BARTON COUNTY, KANSAS
 COMMENCED: 12-26-63
 COMPLETED: 1-1-64

0 -	30	Surface Clay & Rock
30	125	Surface Soil & Clay
125	205	Shale & Clay
205	300	Shale
300	360	Sand
360	835	Redbed & Shale
835	865	Anhydrite
865	1610	Shale & Shells
1610	1850	Lime
1850	2000	Lime & Shale
2000	2085	Shale & Shells
2085	2830	Shale & Lime
2830	3030	Lime & Shale
3030	3072	Lime
3072	3075	Heebner
3075	3385	Lime
3385	3423	Shale & Lime
3423	3450	Arbuckle
3450	3455	Lime
	<u>3455</u>	<u>Rotary Total Depth - D. & A.</u>

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 7 1964
 CONSERVATION DIVISION
 Wichita, Kansas

Set 8 5/8" used surface casing @ 300' Cemented with 185 sacks
 Sunset.

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Reif #1 well, located Southwest Southeast Northwest (SW SE NW) of Section 1, Township 17 South, Range 13 West, Barton County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 6th day of January, 1964.

Ulanda Nichols

Ulanda Nichols, Notary Public

My Commission Expires:
 April 1, 1967