


15.009.01128.00.00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barton County. Sec. 1 Twp. 17 Rge. 13 (E) W (W)
Location as "NE/CNW%SW%" or footage from lines NE NE SE
Lease Owner Lee Phillips Oil Company
Lease Name Nagel Well No. 1
Office Address 1407 Union Nat'l Bank Bldg, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 12, 19 58
Application for plugging filed June 12, 19 58
Application for plugging approved June 12, (verbally) 19 58
Plugging commenced June 12, 19 58
Plugging completed June 12, 19 58
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3449 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	560'	8 5/8"	560'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud from total depth to 300' with plug and 20 sacks of cement at this point. Filled with heavy mud to 35' with plug and 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Harms-Burt Drilling Company
Address P. O. Box 184, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Allan Harms (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Allan Harms
P. O. Box 184, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11 day of July, 19 58
Mary E Van Pelt
Notary Public.
My commission expires 1-20-62

RE
STATE CORP

7-17-58

JUL 17 1958
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 1 T17 R 13W
BOOK PAGE 108 LINE 31

15.009.01128.00.00

DRILLERS LOG

Company: Lee Phillips Oil Co.
Farm: Nagel #1
Commenced: June 2, 1958

NE NE SE Section 1-17-13W
Barton County, Kansas
Completed: June 12, 1958

Elevation: 1970 KB

0 - 90	Post lime
90 - 140	sand & shale
140 - 455	shale
455 - 530	shale & hard sand
530 - 854	Red bed
854 - 890	anhydrite
890 - 1560	shale & shells
1560 - 1700	shale & lime
1700 - 2315	lime & shale
2315 - 2805	shale & lime
2805 - 3025	lime & shale
3025 - 3088	lime
3088 - 3093	Heebner
3093 - 3118	lime & shale
3118 - 3178	Douglas shale
3178 - 3196	Brown Lime
3196 - 3438	Kansas City lime
3438 - 3440	Conglomerate
3440 - 3449	Arbuckle
3449	Total Depth

Set 560' of 8 5/8" surface pipe. Cemented with 400 sacks cement with 2% calcium chloride.

Tops:	Anhydrite	854
	Heebner	3088
	Brown Lime	3178
	Lansing K. C.	3196
	Conglomerate	3438
	Arbuckle	3440

Drill Stem Tests: #1 3201-3223 Open 1 hour. Shut in 30 min. Rec. 7' of mud. BHP 0#

Ran electric log:

Dry, Plugged and Abandoned.

A F F I D A V I T

State of Kansas)
)SS
County of Barton)

I, Allan Harms of the Harms-Buft Drilling Company being first duly sworn on oath state: I have knowledge of the facts, statements and matters herein contained and the same are true and correct.

Allan Harms

Subscribed and sworn to before me this 11 day of July 1958

Mary E. Van Pelt
Notary Public

My commission expires Jan. 20, 1962

PLUGGING
FILE SEC. 1 17 d 13W
BOOK PAGE 108 LINE 31