

15.009.14184.00.01

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Barton SEC. 30 TWP. 17 RGE. 12W E/W
Location as in quarters or footage from lines:
NW SW NE

Locate Well
correctly on above
Section Platt.

Lease Owner Dean Allison Oil Co.
Lease Name Demel #1 Well No. _____
Office Address 507 Insurance Bldg., Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 4/16/81
Plugging completed 4/27/81
Reason for abandonment of well or producing formation Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin
Producing formation _____ Depth to top _____ bottom _____ T.D. 3428'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	271	None
				4 1/2"	3394	1875

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved in. Set in floor. Plugged off bottom with sand to 3100 and 4 sacks cement.
Shot and worked pipe at 2801, 2696, 2611, 2493, 2375, 2250, 2125, 2005 and 1886.
Worked pipe free and pulled total string of 47 joints. Plugged well with 400 lbs hulls, 16 sacks gel, 100 lbs hulls, 25 sacks cement, 4 sacks gel, plug, and 100 sacks cement 50/50 pos 4% gel 3% cc. Plugging complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of April, 1981

My Commission expires:



Joan Kelso
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

APR 29 1981

CONSERVATION DIVISION
Wichita, Kansas

HONAKER DRILLING

#1

DEMEL

30-17-12W
NW SW NE


Contr. HONAKER DRLG BARTON County

E 1889RB Comm. Comp. 10-21-55 IP D & A

Tops	Depth	Datum
HEEB	3052	-1163
BR LM	3142	-1253
LANS	3158	-1269
CH CONG	3401	-1512
ARB	3420	-1531
TD	3428	-1539

Casing
8" 271DST 3287-3328/1½ HR, 360'
HO & WCM, BHP 920#

(W G IVERSEN GEOL.)

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

Dean Allison Oil Co.

No. 1 Demel
washed down the above well -
set 3394 Ft. of 4½" casing
Cement 125 sx 6/10 Poz. 10% salt
Completed 9-18-1979

RECEIVED
STATE OF KANSAS (MISSION)

MAR 23 1981

COMMISSION DIVISION
Wichita, Kansas

11