


15.009.14184.00.00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 30 Twp. 17 Rge. 12 (X) (W)
Location as "NE/CNW/SW" or footage from lines NW SW NE
Lease Owner Honaker Drlg., Inc.
Lease Name Demel Well No. 1
Office Address 2008 Lakin Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-15 1955
Application for plugging filed 10-15 1955
Application for plugging approved 10-15 1955
Plugging commenced 11:30 P. M. 10-15 1955
Plugging completed 2:00 A. M. 10-16 1955
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes - Telephone

Name of Conservation Agent who supervised plugging of this well Merle Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	271'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with heavy rotary mud to 270 feet - 1/3 sack hulls and plug with 20 sacks cement through Drill Pipe - filled hole with heavy rotary mud to 35 feet - 1/3 sack hulls and plug with 15 sacks cement through drill pipe - cement to surface.

RECEIVED
OCT 25 1955
CONSERVATION DIVISION
WICHITA, KANSAS

10-25-55

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Honaker Drlg., Inc.
Address 2008 Lakin Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
S. C. Lincree (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. C. Lincree
2008 Lakin, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of October 1955

My commission expires 6-25-59

Kenneth G. Fischer
Kenneth G. Fischer, Notary Public.

PLUGGING
FILE SEC 30 T 17 R 12 W
BOOK PAGE 10 LINE 13

15.009.14184.00.00

DRILLERS LOG

Well # 1
Loc: NW SW NE
Sec: 30-17S-12W
Barton County, Kansas
Company: Honaker Drig., Inc. et al
Contractor: Honaker Drig., Inc.

Comm: 10-6-55
Comp: 10-15-55
Rotary T D: 3428
Casing: 8 5/8 271'

0	40	Top Soil & Clay	
40	140	Post Rock & Shale	
140	450	Blue Shale	
450	830	Red Bed & Shale	
830	860	Anhydrite	
860	1325	Shale & Shells	8 5/8" casing cemented
1325	1420	Salt & Shale	at 271' with 150 sacks
1420	3158	Lime & Shale	cement and 3 sacks
3158	3245	Lime	calcium chloride.
3245	3428	Lime & Shale	
3428		Total Rotary Depth	

I certify that this is the true and correct copy of the above log, to the best of my knowledge.

H. S. Forbes
H. S. Forbes

Subscribed and sworn to before me this 24th day of October, 1955.

Kenneth G. Fischer
Kenneth G. Fischer, Notary Public

My Commission Expires 6-25-59

PLUGGING
WELL SEC 30 T 17 R 12 W
BOOK PAGE 10 LINE 13

RECORDED
STATE

CONSERVED
WELL