


15.009.01130.00.00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 28 Twp. 17 Rge. 12W (E) (W)
Location as "NE/CNW/SW" or footage from lines SE SE NW
Lease Owner Bennett & Roberts Drilling Co.
Lease Name Hoffman Well No. 1
Office Address Drawer 633, Russell, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 2/10 19 58
Application for plugging filed 2/11 19 58
Application for plugging approved 2/12 19 58
Plugging commenced 2/19 19 58
Plugging completed 2/24 19 58
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3440 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	340'	None
				5 1/2"	3436'	2632.07'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sand to 3430, 5 sx cmt. with dump bailer. Mud to 300', rock brodge, 25 sx cement. Mud to 35', rock bridge, 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
MAR 5 1958
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Great Bend, Ks.

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
Harold Wurst (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Wurst
Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of March, 19 58
Clara Hummel
Notary Public.

My commission expires 6/17/58

PLUGGING
FILE SEC 28T.17 R.12W
BOOK PAGE 81 LINE 42

Bennett & Roberts Drilling Co.
Hoffman #1

SE SE NW Sec. 28-17-12
Barton County, Kansas

R.T.D. 3440'

8 5/8" Set @ 340' w/175 sx cmt.
5 1/2" Set @ 3436' w/125 sx cement

Commenced 1/24/58
Completed 2/5/58

CONTRACTOR: Bennett & Roberts Drilling, Inc.

Surface Soil, Gumbo	60
Sand	75
Shaled post rock	150
Sandy Shale	195
Shale & Shells	325
Blue Shale	340
Shale	480
Red Bed & Shale	778
Anhydrite	820
Red Bed & Shale	1000
Shale & Shells	1470
Shale & Lime Streaks	1515
Shale & Lime	2962
Lime	3055
Lime & Shale	3211
Lime	3357
Lime & Shale	3434
Lime	3440

STATE OF KANSAS)
RUSSELL COUNTY)

I hereby certify that the above information is true and correct to the best of my knowledge.

BENNETT & ROBERTS DRILLING, INC.

By *Bruce Lake*

Subscribed and sworn to before me this 7th day of February, 1958.

Clara Thurman
Notary Public

My Commission Expires 6/17/58

PLUGGING
FILE SEC 281 17 R 120
BOOK PAGE 81 LINE 42

FILED
COMM. OF RUSSELL COUNTY