


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Barton County, Sec. 2 Twp. 17 Rge. 12 (E) (W) x
Location as "NE/CNWxSWx" or footage from lines C E/2 SW/4 SW
Lease Owner Aspen Drilling Co.
Lease Name Meyers Well No. #1
Office Address Box 783, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed 12-1-66 19____
Application for plugging approved _____ 19____
Plugging commenced 12-16-66 19____
Plugging completed 12-19-66 19____
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3361' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Made bottom hole plug back with sand to 3340', mixed and ran 5 sacks cement thru dump bailer.
Mudded hole to 265', set 10' rock bridge. Mixed and ran 5 sacks cement thru dump bailer. Filled hole with 3 1/4 yards ready mix from 240' to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
DEC 21 1966
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 20 day of December, 19 66

My commission expires 24 October 1966
Sidney D Miller
Notary Public.

FEB 13 1967

WELL LOG

CONSERVATION DIVISION
Wichita, Kansas

Aspen Drilling Co.
Box 783
Great Bend, Kansas

MEYERS #1
C E/2 SW SW Sec. 2-17S-12W
Barton County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 11-12-66
Completed: 11-20-66

Casing Record: 8-5/8" @ 263' w/175 sacks Common Cement, 3% CC
5-1/2" @ 3356' w/100 sacks Salt Saturated Cement

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
			1855 Gr.
			1887 D.F.
			1890 K.B.
			<u>FORMATION TOPS</u>
Surface Sand & Shale	0	270	
Sand	270	310	
Shale & Shells	310	360	
Sand	360	395	
Shale, Shells & Red Bed	395	772	
Anhydrite	772	793	Anhydrite 772 +1118
Shale	793	1460	Heebner 2980 -1090
Shale & Lime	1460	2450	Toronto 2995 -1105
Lime & Shale	2450	2645	Douglas 3008 -1118
Lime	2645	2980	Brown Lime 3072 -1182
Shale, Lime & Sand	2980	3072	Lansing 3090 -1200
Lime	3072	3335	Base Kansas City 3335 -1445
Lime & Shale	3335	3354	Arbuckle 3354 -1464
Dolomite	3354	3357	Total Depth 3357 -1467
Total Depth	3357		

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C E/2 SW SW of Section 2-17S-12W, Barton County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

V. Richard Hoover
V. Richard Hoover, President

Subscribed and sworn to before me this 23rd day of November, 1966.

Carmen R. Cook
Carmen R. Cook, Notary Public

My commission expires: Jan. 26, 1967.