

15.009.30318.00.00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 2 Twp. 17S Rge. (E) 12 (W)
Location as "NE/CNWxSWx" or footage from lines SE SW SW
Lease Owner Mayfield-Smith Drilling, Inc.
Lease Name Meyers "A" Well No. 1
Office Address Union Center Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed _____ 19____
Application for plugging filed September 16 19 66
Application for plugging approved _____ 19____
Plugging commenced October 27 19 66
Plugging completed November 2 19 66
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3383 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	265'	8 5/8"	265'	none
		0	3383'	5 1/2"	3383'	2357.70

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pushed plug to 3370', set 10' rock bridge and dumped 5 sacks of cement at 3360'.
Pushed plug to 260'. Set 10' rock bridge. Mixed 4 sacks of cement with 8# of calcium chloride and dumped at 250'. Bailed down hole to bridge and dumped 21 sacks of cement. Filled hole with mud to 40', set 10' rock bridge and capped hole with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
NOV 23 1966
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pipe Pullers, Inc.
Address Box 486, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Dean Wells (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Wells
Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of November, 19 66

My commission expires Feb. 10, 1967

George A Meyer
Notary Public.

15.009.303/8.00.00

RECEIVED
STATE CORPORATION COMMISSION

SEP 19 1966

D R I L L E R S L O G

CONSERVATION DIVISION
Wichita, Kansas

COMPANY	Mayfield & Smith
CONTRACTOR	Aspen Drilling Co.
LEASE NAME	Meyeres #1 "A"
LOCATION	SE SW SW of Sec. 2-T17S-R12W Barton County, Kansas
ELEVATION	1887 K. B.
SURFACE CASING	13 jts. (265') 8 5/8"
OIL STRING	107 jts. (3391.58') 5 1/2"
COMMENCED	December 8, 1965
COMPLETED	December 16, 1965
ROTARY TOTAL DEPTH	3383'

<u>FORMATION</u>	<u>DEPTH</u>	
Clay Shale	150	Spudded @ 7:15 P.M., 12-8-65.
Sandstone	240	Drilled surface hole to 275'. Ran
Red Bed	275	13 jts. 8 5/8" to 265' set with
Clay, Sandstone & Shale	480	175 sx cement, 3% calcium Chloride.
Red Bed & Shale	769	Cement did circulate.
Anhydrite	796	
Red Bed & Shale	1190	DST #1 3082 - 3102
Shale & Shells	1665	DST #2 3108 - 3160
Limestone & Shale	2030	DST #3 3354 - 3363
Shale & Shells	2715	
Limestone & Shale	3048	Ran 107 jts. 3391.58' of new 5 1/2"
Limestone	3102	14# J-55 casing with 125 sx salt
Limestone & Shale	3128	saturated pozmix.
Limestone	3383	
Rotary Total Depth	3383	

FORMATION TOPS

Heebner	2981 (-1094)
Iatan	3075 (-1188)
Lansing	3086 (-1199)

STATE OF KANSAS)
)
COUNTY OF BARTON) SS:

The undersigned, being duly sworn on oath, states that the above statement and log are true and a correct record and log of the well drilled at the location above described.

William S. Schachle
William S. Schachle

Subscribed and sworn to before me this 25th day of August, 1966.

Delores Strecker
Delores Strecker, Notary Public

My Commission expires: August 27, 1969.

