


15.009.30297.00.00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Flat

Barton County. Sec. 2 Twp. 17 Rge. 12 (E) (W)
Location as "NE/CNW/SW" or footage from lines W/2 NE NW
Lease Owner High Plains Production Company
Lease Name Meyers Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 4/10/67 _____ 19____
Plugging completed 4/13/67 _____ 19____
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Truin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3363 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	264	none
				5 1/2	3353	2887

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole and sanded hole to 3060', set 5 sacks of cement. Loaded hole with water, shot pipe at 2891'. Set rock bridge at 260' and ran 5 sacks of cement. Tallied pipe. Bailed hole dry, dumped 20 sacks of cement. Mudded hole to 40' rock bridge and ran 10 sacks of cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

APR 17 1967

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of April, 1967

My commission expires February 15, 1971
Margaret Melcher Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas


COPY
15.009.30297.00.00

Company- MAYFIELD-SMITH DRILLING, INC.
Farm- Meyeres No. 1

SEC. 2 T. 17 R. 12W
CW/2 NE NW

Total Depth. 3363'
Comm. 12-3-64 Comp. 12-9-64
Shot or Treated.
Contractor. Co. Tools
Issued. 6-12-65

County Barton
KANSAS



CASING:

3 5/8" 264' w/145 sx cem.
5 1/2" 3353' w/75 sx cem.

Elevation. 1895' KB

Production. DRY

Figures Indicate Bottom of Formations.

clay, rock	100
sand, shale	264
shale, sand, red bed	765
Anhydrite	795
shale, shells	1440
sdv lime	1484
lime, shale	1930
shale	2130
shale, shells	2530
lime, shale	2960
lime	3153
lime, shale	3267
lime	3357 RTD
lime	3363
Total Depth	

TOPS:
Anhydrite 765
Heebner 2967
Brown lime 3059
Lansing 3078
Arbuckle 3345

RECEIVED
STATE CORPORATION COMMISSION

APR 11 1967

STATE CORPORATION COMMISSION
WICHITA, KANSAS