15.009.01170.00.00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas


WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

NORTH



Locate well correctly on above Section Plat

Barton County. Sec. 27 Twp. 17S Rge. 11W (E) (W)

Location as "NE¼NW¼SW¼" or footage from lines NE-NW-SE

Lease Owner Black Marshall Oil Co.

Lease Name E.H.Norris Well No. 1

Office Address Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 5, 1945 19

Application for plugging filed June 5 19 45

Application for plugging approved June 6 19 45

Plugging commenced June 5, 1945 19

Plugging completed June 6, 1945 19

Reason for abandonment of well or producing formation Dry-No Oil

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W.H.Kerr

Producing formation None Depth to top Bottom Total Depth of Well 3371' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS — CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	240'	Cemented
						85 Sacks

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

The hole was filled with heavy mud to bottom of surface pipe at 240' where the hole was bridged with a wooden plug, and 20-sacks of cement was run on top of the bridge, then heavy mud was put in the hole to 20', hole was bridged and 15-sacks of cement was run to the bottom of the cellar and cellar was cemented.

RECEIVED
STATE CORPORATION COMMISSION
JUN 12 1945
CONSERVATION DIVISION

PLUGGING
FILE SEC 27 T 17 R 11W
BOOK PAGE 15 LINE 28

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Black Marshall Oil Company

Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Walter C Roberts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Walter C Roberts

Claflin, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th. day of June, 19 45

Edwin Wojdziak
Notary Public.

My commission expires February 5, 1947

19-6929 4-43—6M

15.009.01170.00.00

COMPANY: Black-Marshall Oil Company
CONTRACTOR: Ferrell-Young Drilling Company
FARM: E. H. Norris #1

LOCATION: NEc NW¼ SE¼
Section 27-17S-11W
Barton County, Kansas

COMMENCED: May 25, 1945
COMPLETED: June 5, 1945

CASING RECORD:
8 5/8" 236' 85 sax cement

ELEVATION: 1811

PRODUCTION: D & A

FORMATION	DEPTH
Cellar	4
Shale, Shells & Sand	236
Shale	3350
Red Bed	620
Anhydrite	825
Shale & Shells	1160
Salt, Shale, Shells	1270
Shale, Shells, Anhydrite	1460
Lime	1860
Broken Lime	1955
Shale & Shells	2050
Lime & Shale	2285
Shale & Shells	2725
Broken Lime	2790
Lime	2870
Broken Lime	2940
Shale & Shells	3033
Lime	3278
Conglomerate	3341
Arbuckle	3371
Total Depth	3371

TOPS:

Anhydrite	620
Lansing	3030
Conglomerate	3278
Arbuckle	3341
Total Depth	3371

STATE CORPORATION COMMISSION
JUN 12 1945
CONSERVATION DIVISION

I hereby certify this to be a correct and accurate log of the above described well as shown by the drilling report.

PLUGGING
SEC. 27 T. 17 R. 11W
LOC. 15 28

FERRELL-YOUNG DRILLING COMPANY

BY: [signature]

Subscribed and sworn to before me this 8th day of June, 19 45.

[signature]

My commission expires: February 19, 1949.

P. O. Box 6

15.009.01170.00.00

BLACK-MARSHALL OIL CO.

1910 Broadway
GREAT BEND, KANSAS

June 11, 1945

State Corporation Commission
800 Bitting Building
Wichita 2, Kansas

Attention: Mr. H. A. Beverlin

Gentlemen:

For your files we enclose Well Plugging Record in connection with our E. H. Norris #1, NE NW SE Section 27-17S-11W, together with certified copy of log.

Yours very truly

BLACK-MARSHALL OIL CO.

Leon F. Huff

mlh
Enclosures

STATE CORPORATION COMMISSION
JUN 12 1945
CONSERVATION DIVISION

PLUGGING
FILE SC-27-17S-11W
BOOK PAGE 15 LINE 28