


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15.009.00065.00.00  
**WELL PLUGGING RECORD**

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Flat

..... Barton ..... County. Sec. 20 Twp. 17 Rge. 15 (E) (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines ..... NE SE NW  
\* Lease Owner ..... Ben E. Brack Oil Company, Inc.  
Lease Name ..... Ohnmacht ..... Well No. 1  
Office Address ..... 309 Brown Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) ..... Dry Hole  
Date well completed ..... 2-21-52 ..... 19  
Application for plugging filed ..... 2-21-52 ..... 19  
Application for plugging approved ..... 2-21-52 ..... 19  
Plugging commenced ..... 2-21-52 ..... 19  
Plugging completed ..... 2-21-52 ..... 19  
Reason for abandonment of well or producing formation ..... Nothing there

If a producing well is abandoned, date of last production ..... 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? ..... Yes, verbally

Name of Conservation Agent who supervised plugging of this well ..... Harold Hollis  
Producing formation ..... Arbuckle ..... Depth to top ..... 3599' ..... Bottom ? ..... Total Depth of Well ..... 3605' ..... Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Shale, shells, sand, &	Red Rock	0	754	8-5/8"	754'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ..... feet to ..... feet for each plug set.

Filled with heavy mud to 270' and cemented with 20 sacks cement.  
Filled with heavy mud to 35' and cemented with 10 sacks cement to bottom of cellar. Location leveled.

\* (This was a partnership well with Stanolind Oil & Gas Co.)

(If additional description is necessary, use BACK of this sheet)  
Correspondence regarding this well should be addressed to Ben E. Brack Oil Company, Inc.  
Address ..... 309 Brown Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Leland E. Brack (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) *Leland E. Brack*  
309 Brown Bldg., Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 25th day of February, 1952.

*Gertrude Crist*  
Notary Public.

My commission expires June 11, 1955

23-5091-5 8-50-10M



BEN F. BRACK OIL COMPANY, INC.

OHNMAGHT #1

NE SE NW

Sec. 20-17S-15W  
Barton County, Kansas  
Commenced: 2-4-52  
Completed: 2-21-52

Total Depth: 3605'

WELL LOG

Shale - Shells	0 -	558'
Sand & Shale		610'
Sand		705'
Red Rock		755'
Red Rock - Shale		1080'
Anhydrite		1120'
Shale - Shells		1800'
Shale - Lime		2040'
Lime		2112'
Lime (Broken)		2235'
Lime		2290'
(Broken) Lime - Shale		2555'
Shale - Lime		2815'
Lime - Shale		3025'
Lime		3333'
Brown Lime		3381'
Lime		3500'
Lime - Shale (Streaks)		3537'
Lime - Conglomerate		3570'
Conglomerate		3599'
Arbuckle		3605' T.D.

FORMATIONS

Anhydrite	1088'
Heebner	3273'
Brown Lime	3333'
Kansas City	3353'
Conglomerate	3465'
Arbuckle	3599'

Above depths denote bottom of formation.

D & A

CASING

8-5/8" 754'

To the best of my knowledge the above is a true and correct statement of all formations and where found.

BEN F. BRACK OIL COMPANY, INC.

Leland E. Brack  
Leland E. Brack

WITNESSED:

Gertrude Crest

FEB 26 1952

**PLUGGING**  
FILE SEC 20 T 17 R 15W  
PAGE 146 LINE 10