

15.009.00995.00.00

WELL PLUGGING RECORD

STATE OF KANSAS STATE CORPORATION COMMISSION

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 800 Bitting Building Wichita, Kansas

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

Barton

County. Sec. 24 Twp. 17 Rge. (E) 14 (W)

Location as "NE1/4NW1/4SW1/4" or footage from lines 330' S. & 330' W. of center Sec 24

Lease Owner British American Oil Prod. Co. & Leasing Co. Corp.

Lease Name Frank Linder Estate Well No. 1

Office Address Phillower Bldg. Tulsa, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date, well completed. 19 41

Application for plugging filed. Jan. 19, 19 41

Application for plugging approved. Jan. 23, 19 41

Plugging Commenced. Jan. 19, 19 41

Plugging Completed. Jan. 20, 19 41

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well C. T. Alexander

Producing formation. Arkuckle Lime Depth to top. 3449 Bottom. 3507 Total Depth of Well. 3507 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: Surface, 255', 10 3/4", None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from... feet to ... feet for each plug set.

Hole filled with mud from 3507 to 255, hole bridged at 255, cemented to 240, mud to 14 feet and cement to 8 feet, a total of 25 sacks of cement used.

1-28-41

PLUGGING FILE SEC. 24, 17, 14E BOOK PAGE 127 LINE 26

STATE OF KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The British American Oil Producing Co. Address Phillower Building, Tulsa, Oklahoma

STATE OF Kansas COUNTY OF Stafford ss. employee of owner

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

(Address)

SUBSCRIBED AND SWORN to before me this 25 day of Jan, 19 41

May 17 - 1941

[Signature] Notary Public.

My commission expires

15.009.00285.00.00

THE BRITISH-AMERICAN OIL PRODUCING COMPANY

PHILTOWER BUILDING

TULSA, OKLAHOMA

January 27, 1941

State Corporation Commission
Bitting Building
Wichita, Kansas

Gentlemen:

We are enclosing Well Plugging Record, duly executed by this company, covering the British American Oil Producing Company Frank Linder well No. 1, located in Section 24-17-14, Barton County, Kansas.

Yours very truly,

C. E. Wright
C. E. Wright
General Superintendent

CEW:rl

cc R. B. Wheeler

PLUGGING
FILE SEC 24-17-R-146
BOOK PAGE 127 LINE 26

JAN 29 1941
STATE CORP. COM.
CONSERV. DIV.

15.009.00995.00.00

THE BRITISH AMERICAN OIL PRODUCING COMPANY

KANSAS DISTRICT FIELD OFFICE
CODELL, KANSAS
February 4, 1941

Kansas State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

Attention: Mr. T. A. Morgan, Dir.


Dear Sir:

In response to your letter of January 31st, to our Tulsa office, we have been directed to send you the item required, the same being the well log of our Frank Linder Estate No. 1 well, which was a dry hole and plugged and abandoned.

You will find the well log attached hereto.

Yours truly,


R. B. Wheeler
Dist. Superintendent

By 
Dist. Field Clerk

LB:b

Attach.

PLUGGING
FILE SEC 24.17.14U
BOOK PAGE 129 LINE 26-



15.009.00995.00.00

THE BRITISH-AMERICAN OIL PRODUCING COMPANY

FRANK LINDER NO. 1

WELL LOG

LOCATION: 330' south and 330' west of the center of Section 24-17S-14W,
Barton County, Kansas.

Ground Elevation	1830.53'
Total Depth	3507'
Top Arbuckle	3449'
Initial Potential	None (Dry Hole)
Drilling Commenced	12-29-40
Drilling Completed	1-17-41

10-3/4" OD casing was set at 254' and cemented with
75 sacks of cement.
No oil string set.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Broken Lime	0	18
Blue Shale	18	152
Sand	152	162
Red Mud	162	183
Red Rock	183	205
Blue Shale	205	220
Red Rock	220	240
Sand	240	245
Red Rock	245	255
Blue Shale	255	330
Sand	330	375
Sticky Shale	375	585
Clay, Shale & Shells	585	775
Shale & Shells	775	845
Anhydrite	845	880
Lime	880	940
Shale & Shells	940	1020
Shale	1020	1050
Red Bed	1050	1115
Broken Lime	1115	1160
Shale & Shells	1160	1375
Broken Sand	1375	1575
Sandy Lime & Shale	1575	1630
Sandy Lime	1630	1765
Lime	1765	1830
Shale	1830	1850
Sand	1850	1900
Sandy Lime	1900	2050
Lime	2050	2070
Shale	2070	2080
Hard Sand	2080	2100
Sandy Shale	2100	2115
Lime	2115	2141
Soft Sandy Lime	2141	2146
Broken Lime	2146	2180
Sandy Lime	2180	2400
Sandy Lime & Shale	2400	2455
Sandy Lime	2455	2565
Shale	2565	2610
Sand	2610	2680
Sandy Lime	2680	2800
Lime	2800	3212'
Kansas City Lime	3212'	3360
Lime	3360	3414
Conglomerate	3414	3449
Arbuckle Lime	3449	3507

PLUGGING	
FILE	FC 24-17-14W
BOOK	PAGE 127 LINE 26

Plugged & Abandoned 1-21-41