



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

SEP 16 1974

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Elmer Zimmerman of Woodman & Iannitti Drlg. Co has this date requested permission to plug the following described well:

Mr. Joe Brougher guarantees payment of the plugging fee.

Operator's full Name: Joe Brougher

Complete Address: Great Bend, Kansas 67530

Lease Name: Smith Well No. # 1

Location: SE NW SW Sec. 19 Twp. 20 Rge. 14 (E)(W) W

County: Barton Total Depth 3633 Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Elmer Zimmerman was instructed to plug the well as follows:

8 5/8" csg. 872' Cwc. with 450 sax cmt.

Circulated hole with heavy mud to 600', set plug, & displaced 40 sax

cement thru drill pipe. Mud to 300' & displaced 30 sax cement thru

drill pipe. Mud to 40', 1/2 sax hulls, plug, & 15 sax cement with

Halliburton Cementing Company's pump truck, cementing to base of cellar.

Very truly yours,

Don Leonard  
Conservation Division Agent