



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 6 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Roger L. Messman of Messman & Rinehart Oil Co. has this date requested permission to plug the following described well:

Mr. Messman & Rinehart Oil guarantees payment of the plugging fee.

Operator's full Name: Messman & Rinehart Oil Company

Complete Address: 1432 Wichita Plaza, Wichita, Kansas 67202

Lease Name: Ira Unruh Well No. # 1

Location: NE SE NW Sec. 15 Twp. 20 Rge. 14 (E)(W) W

County: Barton Total Depth 3580 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Russ Sullivan was instructed to plug the well as follows:

8 5/8" csg. 822' Cwc. Perf. 3547'.

Sanded hole back to 3535' & dumped 4 sax cement with dump bailer.

Pulled pipe. Mud to 370', set 20' rock bridge, & displaced 5 yds.

Ready-mix Cement, cementing from 350' to base of cellar.

Very truly yours,

Don. L. Brian  
Conservation Division Agent