

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 27 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Aspen Drilling Company

Complete Address: Box 783, Great Bend, Kansas

Lease Name Meyers Well No. # 1

Location C E/2 SW SW Sec. 2 Twp. 17 Rge. 12 (E) (W) W

County Barton Total Depth 3361

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Company

Address: Box 364, Great Bend, Kansas License No. # 399

Operation Completed: Hour 10 AM Day 19 Month 12 Year 1966

The Above well was plugged as follows:

8 5/8" 269' Cwc.

Sanded hole back to 3340' & dumped 5 sax cement with dump bailer. Pulled pipe. Mud to
269', set 15' rock bridge, & displaced 5 sax cement. Let set over night. Bailed hole
dry & displaced 3 1/4 yds. ready-mix cement, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Don Truman
Well Plugging Supervisor

DATE 12/27/66

INV. NO. 4515-112