

15.009.30297.00.00

Form CP-3
Rev. 6-26-62

KANSAS

Handwritten mark

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 18 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name High Plains Production Company

Complete Address: 304 Insurance Bldg., Wichita, Kansas 67202

Lease Name Meyers Well No. # 1

Location W/2 NE NW Sec. 2 Twp. 17 Rge. 12 (E) (W) W

County Barton Total Depth 3363

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. # 396

Operation Completed: Hour 12 AM Day 13 Month 4 Year 1967

The Above well was plugged as follows:

8 5/8" 264' Cwc.
Set bottom plug @ 3060' & dumped 5 sax cement with dump bailer. Pulled pipe.
Mudded hole to 260', set rock bridge, & dumped 5 sax cement. Let set over night,
bailed hole dry, & displaced 20 sax cement. Mud to 40', set 10' rock bridge, &
displaced 10 sax cement cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 4/18/67
INV. NO. 5068-W

Signed: Don Leonard
Well Plugging Supervisor