



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 99-24

LOCATION S W. 22 W. - 22 E

SEC. 26 TWP. 19 RGE. 14 - W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 2 Lease Emiller

Operator John S. Storkoff Address 2916 Forest Cos. St. Bend-Kans.

Field \_\_\_\_\_ County Barton

Total Depth 3480 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/4" - 801 ft. Circulated with cement  
5/8" casing set at 3475 ft. 12 1/2 sacks of cement  
Lame with Plug at 3364 ft. sand at 3330 ft. Dumped  
5 sacks of cement at 3330 ft. Shot off & pulled the  
5/8" casing - mud to 250 ft. Set rock bridge &  
10 sacks of cement at 250 ft. mud to 35 ft. Plug  
& 10 sacks of cement at the surface.

The West Supply Co. - Plugging Contractors

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 23 1953

CONSERVATION DIVISION  
Wichita, Kansas

C. D. Storkoff  
District Conservation Agent

Date 5-21-53

**PLUGGING**  
FILE SEC 26 T 19 R 14W  
BOOK PAGE 22 LINE 24

5-23-53